

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐

<b>APPLICATION FOR PERMIT TO DRILL</b>						<b>1. WELL NAME and NUMBER</b> GMBU 104-5-9-17			
<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						<b>3. FIELD OR WILDCAT</b> MONUMENT BUTTE			
<b>4. TYPE OF WELL</b> Oil Well Coalbed Methane Well: NO						<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b> GMBU (GRRV)			
<b>6. NAME OF OPERATOR</b> NEWFIELD PRODUCTION COMPANY						<b>7. OPERATOR PHONE</b> 435 646-4825			
<b>8. ADDRESS OF OPERATOR</b> Rt 3 Box 3630 , Myton, UT, 84052						<b>9. OPERATOR E-MAIL</b> mcrozier@newfield.com			
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> UTU-020252			<b>11. MINERAL OWNERSHIP</b> FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>			
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b>						<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>			
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b>						<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>			
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>			<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			<b>19. SLANT</b> VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>			

20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	483 FSL 663 FWL	SWSW	32	8.0 S	17.0 E	S
Top of Uppermost Producing Zone	122 FSL 660 FWL	SWSW	32	8.0 S	17.0 E	S
At Total Depth	182 FNL 660 FWL	NWNW	5	9.0 S	17.0 E	S

<b>21. COUNTY</b> DUCHESNE		<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 182		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 10	
		<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 842		<b>26. PROPOSED DEPTH</b> MD: 6298 TVD: 6258	
<b>27. ELEVATION - GROUND LEVEL</b> 5245		<b>28. BOND NUMBER</b> WYB000493		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> 437478	

Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Surf	12.25	8.625	0 - 300	24.0	J-55 ST&C	8.3	Class G	138	1.17	15.8
Prod	7.875	5.5	0 - 6298	15.5	J-55 LT&C	8.3	Premium Lite High Strength	297	3.43	11.0
							50/50 Poz	363	1.24	14.4

**ATTACHMENTS**

**VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP

<b>NAME</b> Mandie Crozier	<b>TITLE</b> Regulatory Tech	<b>PHONE</b> 435 646-4825
<b>SIGNATURE</b>	<b>DATE</b> 01/21/2013	<b>EMAIL</b> mcrozier@newfield.com
<b>API NUMBER ASSIGNED</b> 43013519770000		
<b>APPROVAL</b>  Permit Manager		

RECEIVED: March 04, 2013

NEWFIELD PRODUCTION COMPANY  
GMBU 104-5-9-17  
AT SURFACE: SW/SW SECTION 32, T8S R17E  
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 1505'
Green River	1505'
Wasatch	6230'
<b>Proposed TD</b>	<b>6298'</b>

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1505' – 6230'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO <sub>3</sub> ) (mg/l)
Dissolved Bicarbonate (NaHCO <sub>3</sub> ) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO <sub>4</sub> ) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

**a. Casing Design: GMBU 104-5-9-17**

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	300'	24.0	J-55	STC	2,950 17.53	1,370 14.35	244,000 33.89
Prod casing 5-1/2"	0'	6,298'	15.5	J-55	LTC	4,810 2.40	4,040 2.02	217,000 2.22

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg  
 Pore pressure at surface casing shoe = 8.33 ppg  
 Pore pressure at prod casing shoe = 8.33 ppg  
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

**b. Cementing Design: GMBU 104-5-9-17**

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft <sup>3</sup> /sk)
			ft <sup>3</sup>			
Surface casing	300'	Class G w/ 2% CaCl	138 161	30%	15.8	1.17
Prod casing Lead	4,298'	Prem Lite II w/ 10% gel + 3% KCl	297 968	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

\*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to  $\pm 300$  feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about  $\pm 300$  feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated



bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the second quarter of 2013, and take approximately seven (7) days from spud to rig release.




<b>NAD 83 (BOTTOM HOLE LOCATION)</b>
LATITUDE = 40°04'59.90"
LONGITUDE = 110°02'15.01"
<b>NAD 27 (BOTTOM HOLE LOCATION)</b>
LATITUDE = 40°05'00.03"
LONGITUDE = 110°02'12.47"

REGISTERED LAND SURVEYOR  
REGISTRATION No. 100037  
STATE OF UTAH

RECEIVED: January 21, 2013



## Access Road Map



**Tri State**  
**Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
 F: (435) 781-2518



## NEWFIELD EXPLORATION COMPANY

2-32-8-17 (Existing Well)  
 104-5-9-17 (Proposed Well)  
 128-32-8-17 (Proposed Well)  
 SEC. 32, T8S, R17E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: D.C.R. REVISED: 12-07-12 A.P.C. VERSION:

DATE: 11-08-2012

SCALE: 1:100,000

**V2**


**TOPOGRAPHIC MAP**

SHEET

**A**



## Access Road Map



## Legend

Existing Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State  
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

2-32-8-17 (Existing Well)  
104-5-9-17 (Proposed Well)  
128-32-8-17 (Proposed Well)  
SEC. 32, T8S, R17E, S.L.B.&M. Duchesne County, UT.

DRAWN BY: D.C.R. REVISED: 12-07-12 A.P.C. VERSION:

DATE: 11-08-2012

SCALE: 1" = 2,000'

**V2**

**TOPOGRAPHIC MAP**

SHEET

**B**



# Proposed Pipeline Map

2-32-8-17 (Existing Well)  
104-5-9-17 (Proposed Well)  
128-32-8-17 (Proposed Well)

Existing  
Gas Pipeline

Existing  
Flowline

Existing  
Waterline

## Legend

Existing Road

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

**Tri State**  
**Land Surveying, Inc.**  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
F: (435) 781-2518



## NEWFIELD EXPLORATION COMPANY

2-32-8-17 (Existing Well)  
104-5-9-17 (Proposed Well)  
128-32-8-17 (Proposed Well)  
SEC. 32, T8S, R17E, S.L.B.&M. Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	12-07-12 A.P.C.	VERSION:
DATE:	11-08-2012			V2
SCALE:	1" = 2,000'			

**TOPOGRAPHIC MAP**


SHEET

**C**



**Exhibit "B" Map**

2-32-8-17 (Existing Well)  
 104-5-9-17 (Proposed Well)  
 128-32-8-17 (Proposed Well)



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

**Tri State**  
**Land Surveying, Inc.**  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501  
 F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

2-32-8-17 (Existing Well)  
 104-5-9-17 (Proposed Well)  
 128-32-8-17 (Proposed Well)  
 SEC. 32, T8S, R17E, S.L.B.&M. Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	12-07-12 A.P.C.	VERSION:
DATE:	11-08-2012			<b>V2</b>
SCALE:	1" = 2,000'			

**TOPOGRAPHIC MAP**

SHEET

**D**



# **NEWFIELD EXPLORATION**

**USGS Myton SW (UT)  
SECTION 32 T8S, R17E  
104-5-9-17**

**Wellbore #1**

**Plan: Design #1**

## **Standard Planning Report**

**08 November, 2012**







# Payzone Directional Planning Report



<b>Database:</b>	EDM 2003.21 Single User Db	<b>Local Co-ordinate Reference:</b>	Well 104-5-9-17
<b>Company:</b>	NEWFIELD EXPLORATION	<b>TVD Reference:</b>	104-5-9-17 @ 5257.0ft (Original Well Elev)
<b>Project:</b>	USGS Myton SW (UT)	<b>MD Reference:</b>	104-5-9-17 @ 5257.0ft (Original Well Elev)
<b>Site:</b>	SECTION 32 T8S, R17E	<b>North Reference:</b>	True
<b>Well:</b>	104-5-9-17	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Design #1		

<b>Project</b>	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	Utah Central Zone		

<b>Site</b>	SECTION 32 T8S, R17E, SEC 32 T8S, R17E			
<b>Site Position:</b>		<b>Northing:</b>	7,197,024.42 ft	<b>Latitude:</b> 40° 4' 6.630 N
<b>From:</b>	Lat/Long	<b>Easting:</b>	2,049,704.59 ft	<b>Longitude:</b> 110° 2' 14.800 W
<b>Position Uncertainty:</b>	0.0 ft	<b>Slot Radius:</b>	"	<b>Grid Convergence:</b> 0.94 °

<b>Well</b>	104-5-9-17, SHL LAT: 40 04 06.47 LONG: -110 02 14.95			
<b>Well Position</b>	<b>+N/-S</b>	-16.2 ft	<b>Northing:</b>	7,197,008.03 ft
	<b>+E/-W</b>	-11.7 ft	<b>Easting:</b>	2,049,693.19 ft
<b>Position Uncertainty</b>		0.0 ft	<b>Wellhead Elevation:</b>	5,257.0 ft
			<b>Ground Level:</b>	5,245.0 ft

<b>Wellbore</b>	Wellbore #1				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2010	11/8/2012	11.13	65.78	52,150

<b>Design</b>	Design #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PROTOTYPE	<b>Tie On Depth:</b>	0.0
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.0	0.0	0.0	179.43

<b>Plan Sections</b>										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,065.8	6.99	179.43	1,064.7	-28.4	0.3	1.50	1.50	0.00	179.43	
5,005.4	6.99	179.43	4,975.0	-507.6	5.0	0.00	0.00	0.00	0.00	104-5-9-17 TGT
6,298.0	6.99	179.43	6,258.0	-664.8	6.6	0.00	0.00	0.00	0.00	



# Payzone Directional Planning Report



<b>Database:</b>	EDM 2003.21 Single User Db	<b>Local Co-ordinate Reference:</b>	Well 104-5-9-17
<b>Company:</b>	NEWFIELD EXPLORATION	<b>TVD Reference:</b>	104-5-9-17 @ 5257.0ft (Original Well Elev)
<b>Project:</b>	USGS Myton SW (UT)	<b>MD Reference:</b>	104-5-9-17 @ 5257.0ft (Original Well Elev)
<b>Site:</b>	SECTION 32 T8S, R17E	<b>North Reference:</b>	True
<b>Well:</b>	104-5-9-17	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	179.43	700.0	-1.3	0.0	1.3	1.50	1.50	0.00
800.0	3.00	179.43	799.9	-5.2	0.1	5.2	1.50	1.50	0.00
900.0	4.50	179.43	899.7	-11.8	0.1	11.8	1.50	1.50	0.00
1,000.0	6.00	179.43	999.3	-20.9	0.2	20.9	1.50	1.50	0.00
1,065.8	6.99	179.43	1,064.7	-28.4	0.3	28.4	1.50	1.50	0.00
1,100.0	6.99	179.43	1,098.6	-32.5	0.3	32.5	0.00	0.00	0.00
1,200.0	6.99	179.43	1,197.8	-44.7	0.4	44.7	0.00	0.00	0.00
1,300.0	6.99	179.43	1,297.1	-56.9	0.6	56.9	0.00	0.00	0.00
1,400.0	6.99	179.43	1,396.4	-69.0	0.7	69.0	0.00	0.00	0.00
1,500.0	6.99	179.43	1,495.6	-81.2	0.8	81.2	0.00	0.00	0.00
1,600.0	6.99	179.43	1,594.9	-93.3	0.9	93.4	0.00	0.00	0.00
1,700.0	6.99	179.43	1,694.1	-105.5	1.0	105.5	0.00	0.00	0.00
1,800.0	6.99	179.43	1,793.4	-117.7	1.2	117.7	0.00	0.00	0.00
1,900.0	6.99	179.43	1,892.7	-129.8	1.3	129.8	0.00	0.00	0.00
2,000.0	6.99	179.43	1,991.9	-142.0	1.4	142.0	0.00	0.00	0.00
2,100.0	6.99	179.43	2,091.2	-154.2	1.5	154.2	0.00	0.00	0.00
2,200.0	6.99	179.43	2,190.4	-166.3	1.7	166.3	0.00	0.00	0.00
2,300.0	6.99	179.43	2,289.7	-178.5	1.8	178.5	0.00	0.00	0.00
2,400.0	6.99	179.43	2,388.9	-190.7	1.9	190.7	0.00	0.00	0.00
2,500.0	6.99	179.43	2,488.2	-202.8	2.0	202.8	0.00	0.00	0.00
2,600.0	6.99	179.43	2,587.5	-215.0	2.1	215.0	0.00	0.00	0.00
2,700.0	6.99	179.43	2,686.7	-227.2	2.3	227.2	0.00	0.00	0.00
2,800.0	6.99	179.43	2,786.0	-239.3	2.4	239.3	0.00	0.00	0.00
2,900.0	6.99	179.43	2,885.2	-251.5	2.5	251.5	0.00	0.00	0.00
3,000.0	6.99	179.43	2,984.5	-263.6	2.6	263.7	0.00	0.00	0.00
3,100.0	6.99	179.43	3,083.7	-275.8	2.7	275.8	0.00	0.00	0.00
3,200.0	6.99	179.43	3,183.0	-288.0	2.9	288.0	0.00	0.00	0.00
3,300.0	6.99	179.43	3,282.3	-300.1	3.0	300.2	0.00	0.00	0.00
3,400.0	6.99	179.43	3,381.5	-312.3	3.1	312.3	0.00	0.00	0.00
3,500.0	6.99	179.43	3,480.8	-324.5	3.2	324.5	0.00	0.00	0.00
3,600.0	6.99	179.43	3,580.0	-336.6	3.3	336.7	0.00	0.00	0.00
3,700.0	6.99	179.43	3,679.3	-348.8	3.5	348.8	0.00	0.00	0.00
3,800.0	6.99	179.43	3,778.5	-361.0	3.6	361.0	0.00	0.00	0.00
3,900.0	6.99	179.43	3,877.8	-373.1	3.7	373.1	0.00	0.00	0.00
4,000.0	6.99	179.43	3,977.1	-385.3	3.8	385.3	0.00	0.00	0.00
4,100.0	6.99	179.43	4,076.3	-397.5	4.0	397.5	0.00	0.00	0.00
4,200.0	6.99	179.43	4,175.6	-409.6	4.1	409.6	0.00	0.00	0.00
4,300.0	6.99	179.43	4,274.8	-421.8	4.2	421.8	0.00	0.00	0.00
4,400.0	6.99	179.43	4,374.1	-434.0	4.3	434.0	0.00	0.00	0.00
4,500.0	6.99	179.43	4,473.3	-446.1	4.4	446.1	0.00	0.00	0.00
4,600.0	6.99	179.43	4,572.6	-458.3	4.6	458.3	0.00	0.00	0.00
4,700.0	6.99	179.43	4,671.9	-470.4	4.7	470.5	0.00	0.00	0.00
4,800.0	6.99	179.43	4,771.1	-482.6	4.8	482.6	0.00	0.00	0.00
4,900.0	6.99	179.43	4,870.4	-494.8	4.9	494.8	0.00	0.00	0.00
5,005.4	6.99	179.43	4,975.0	-507.6	5.0	507.6	0.00	0.00	0.00
5,100.0	6.99	179.43	5,068.9	-519.1	5.2	519.1	0.00	0.00	0.00
5,200.0	6.99	179.43	5,168.1	-531.3	5.3	531.3	0.00	0.00	0.00



## Payzone Directional

## Planning Report




<b>Database:</b>	EDM 2003.21 Single User Db	<b>Local Co-ordinate Reference:</b>	Well 104-5-9-17
<b>Company:</b>	NEWFIELD EXPLORATION	<b>TVD Reference:</b>	104-5-9-17 @ 5257.0ft (Original Well Elev)
<b>Project:</b>	USGS Myton SW (UT)	<b>MD Reference:</b>	104-5-9-17 @ 5257.0ft (Original Well Elev)
<b>Site:</b>	SECTION 32 T8S, R17E	<b>North Reference:</b>	True
<b>Well:</b>	104-5-9-17	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	Wellbore #1		
<b>Design:</b>	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	6.99	179.43	5,267.4	-543.4	5.4	543.5	0.00	0.00	0.00
5,400.0	6.99	179.43	5,366.7	-555.6	5.5	555.6	0.00	0.00	0.00
5,500.0	6.99	179.43	5,465.9	-567.8	5.6	567.8	0.00	0.00	0.00
5,600.0	6.99	179.43	5,565.2	-579.9	5.8	580.0	0.00	0.00	0.00
5,700.0	6.99	179.43	5,664.4	-592.1	5.9	592.1	0.00	0.00	0.00
5,800.0	6.99	179.43	5,763.7	-604.3	6.0	604.3	0.00	0.00	0.00
5,900.0	6.99	179.43	5,862.9	-616.4	6.1	616.4	0.00	0.00	0.00
6,000.0	6.99	179.43	5,962.2	-628.6	6.3	628.6	0.00	0.00	0.00
6,100.0	6.99	179.43	6,061.5	-640.7	6.4	640.8	0.00	0.00	0.00
6,200.0	6.99	179.43	6,160.7	-652.9	6.5	652.9	0.00	0.00	0.00
6,298.0	6.99	179.43	6,258.0	-664.8	6.6	664.9	0.00	0.00	0.00

API Well Number: 43013519770000





Project: USGS Myton SW (UT)  
 Site: SECTION 32 T8S, R17E  
 Well: 104-5-9-17  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.13°

Magnetic Field  
 Strength: 52150.4snT  
 Dip Angle: 65.78°  
 Date: 11/8/2012  
 Model: IGRF2010



## WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
104-5-9-17 TGT	4975.0	-507.6	5.0	Circle (Radius: 75.0)

## SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1065.8	6.99	179.43	1064.7	-28.4	0.3	1.50	179.43	28.4	
4	5005.4	6.99	179.43	4975.0	-507.6	5.0	0.00	0.00	507.6	104-5-9-17 TGT
5	6298.0	6.99	179.43	6258.0	-664.8	6.6	0.00	0.00	664.9	



**NEWFIELD PRODUCTION COMPANY  
GMBU 104-5-9-17  
AT SURFACE: SW/SW SECTION 32, T8S R17E  
DUCHESNE COUNTY, UTAH**

**ONSHORE ORDER NO. 1**

**MULTI-POINT SURFACE USE & OPERATIONS PLAN**

**1. EXISTING ROADS**

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU 104-5-9-17 located in the SW 1/4 SW 1/4 Section 32, T8S, R17E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 – 1.4 miles  $\pm$  to the junction of this highway and UT State Hwy 53; proceed in a southeasterly direction – 10.0 miles  $\pm$  to it's junction with an existing road to the southwest; proceed in a southwesterly direction – 0.4 miles  $\pm$  to it's junction with an existing road to the northwest; proceed in a northwesterly direction – 0.2 miles  $\pm$  to it's junction with the beginning of the access road to the existing 2-32-8-17 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

**2. PLANNED ACCESS ROAD**

There is no proposed access road for this location. The proposed well will be drilled directionaly off of the existing 2-32-8-17 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

**3. LOCATION OF EXISTING WELLS**

Refer to Exhibit "B".

**4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District  
Water Right : 43-7478

Maurice Harvey Pond  
Water Right: 47-1358

Neil Moon Pond  
Water Right: 43-11787

Newfield Collector Well  
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A 16 mil liner with felt is required. Please refer to the Greater Monument Butte Green River Development SOP.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

**Fencing Requirements**

- a) All pits will be fenced or have panels installed consistent with the following minimum standards:
  1. The wire shall be no more than two (2) inches above the ground. If barbed wire is utilized it will be installed three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
  2. Corner posts shall be centered and/or braced in such a manner to keep tight and upright at all times
  3. Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

**10. PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

**11. SURFACE OWNERSHIP – State of Utah.**

**12. OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. State of Utah Antiquities Project Permit # U-08-MQ-0236s 4/22/08, prepared by Montgomery Archaeological Consultants. . Paleontological Resource Survey prepared by, Wade Miller, 10/10/12. See attached report cover pages, Exhibit "D".

**Water Disposal**

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

**Additional Surface Stipulations**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

**Details of the On-Site Inspection**

The proposed GMBU 104-5-9-17 was on-sited on 12/20/12. The following were present; Corie Miller (Newfield Production), Mandie Crozier (Newfield Production), and Sheri Wysong (Bureau of Land Management).

**Hazardous Material Declaration**

Newfield Production Company guarantees that during the drilling and completion of the GMBU 104-5-9-17, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU 104-5-9-17, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**  
**Representative**

Name: Corie Miller  
Address: Newfield Production Company  
Route 3, Box 3630  
Myton, UT 84052  
Telephone: (435) 646-3721

**Certification**

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #104-5-9-17, Section 32, Township 8S, Range 17E: Lease UTU-020252 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.


I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

1/18/13  
Date

\_\_\_\_\_  
Mandie Crozier  
Regulatory Analyst  
Newfield Production Company



## Typical 2M BOP stack configuration



2M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY

# NEWFIELD EXPLORATION COMPANY

## TOP HOLE FOOTAGES

104-5-9-17 (PROPOSED)

483' FSL &amp; 663' FWL

128-32-8-17 (PROPOSED)

466' FSL &amp; 651' FWL

## WELL PAD INTERFERENCE PLAT

2-32-8-17 (Existing Well)

104-5-9-17 (Proposed Well)

128-32-8-17 (Proposed Well)

Pad Location: SWSW Section 32, T8S, R17E, S.L.B.&amp;M.

## LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
2-32-8-17	40° 04' 06.80"	110° 02' 14.64"
P-32-8-17	40° 04' 06.63"	110° 02' 14.80"
104-5-9-17	40° 04' 06.47"	110° 02' 14.95"
128-32-8-17	40° 04' 06.30"	110° 02' 15.11"

## LATITUDE & LONGITUDE Center of Pattern (NAD 83)

WELL	LATITUDE	LONGITUDE
104-5-9-17	40° 04' 01.45"	110° 02' 15.00"
128-32-8-17	40° 04' 13.48"	110° 02' 14.56"

## LATITUDE & LONGITUDE Bottom Hole Position (NAD 83)

WELL	LATITUDE	LONGITUDE
104-5-9-17	40° 03' 59.90"	110° 02' 15.01"
128-32-8-17	40° 04' 15.71"	110° 02' 14.38"

## RELATIVE COORDINATES From Top Hole to Bottom Hole

WELL	NORTH	EAST
104-5-9-17	-665'	7'
128-32-8-17	954'	41'

## CENTER OF PATTERN FOOTAGES

104-5-9-17 (PROPOSED)

25' FNL &amp; 660' FWL


128-32-8-17 (PROPOSED)

1192' FSL &amp; 694' FWL

### Note:

Bearings are  
based on GPS  
Observations.

SURVEYED BY: Q.M.	DATE SURVEYED: 11-05-12	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 11-06-12	V2
SCALE: 1" = 60'	REVISED: F.T.M. 12-07-12	



# NEWFIELD EXPLORATION COMPANY

## LOCATION LAYOUT

2-32-8-17 (Existing Well)


104-5-9-17 (Proposed Well)

128-32-8-17 (Proposed Well)

Pad Location: SWSW Section 32, T8S, R17E, S.L.B.&M.

### Berm Note:

Construct 2' High berm around Perimeter of pad, Except when Cut Exceeds 2'. Blend New Constructed berm into Existing Pad berm where Required.



### NOTE:





The topsoil & excess material areas are calculated as being mounds containing 1,340 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.

### Note:

Topsoil to be Stripped From All New Construction Areas and Proposed Stockpile Locations

SURVEYED BY: Q.M.	DATE SURVEYED: 11-05-12	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 11-06-12	V2
SCALE: 1" = 60'	REVISED: F.T.M. 12-07-12	

**Tri State** (435) 781-2501  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

**NEWFIELD EXPLORATION COMPANY****CROSS SECTIONS****2-32-8-17 (Existing Well)****104-5-9-17 (Proposed Well)****128-32-8-17 (Proposed Well)***Pad Location: SWSW Section 32, T8S, R17E, S.L.B.&M.*

NOTE:  
UNLESS OTHERWISE  
NOTED ALL CUT/FILL  
SLOPES ARE AT 1.5:1


**ESTIMATED EARTHWORK QUANTITIES**  
(No Shrink or swell adjustments have been used)  
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	160	40	Topsoil is not included in Pad Cut	120
PIT	690	0		690
TOTALS	850	40	410	810

SURVEYED BY: Q.M.	DATE SURVEYED: 11-05-12	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 11-06-12	V2
SCALE: 1" = 60'	REVISED: F.T.M. 12-07-12	

**Tri State**  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078  
(435) 781-2501

**RECEIVED:** January 21, 2013


**NEWFIELD EXPLORATION COMPANY****TYPICAL RIG LAYOUT****2-32-8-17 (Existing Well)****104-5-9-17 (Proposed Well)****128-32-8-17 (Proposed Well)***Pad Location: SWSW Section 32, T8S, R17E, S.L.B.&M.*

*Note:*  
Flare pit is to be located a Minimum of 100' from the Proposed Well Head.

SURVEYED BY: Q.M.	DATE SURVEYED: 11-05-12	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 11-06-12	V2
SCALE: 1" = 60'	REVISED: F.T.M. 12-07-12	

**Tri State** (435) 781-2501  
Land Surveying, Inc.  
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 21, 2013

***NEWFIELD EXPLORATION COMPANY******RECLAMATION LAYOUT******2-32-8-17 (Existing Well)******104-5-9-17 (Proposed Well)******128-32-8-17 (Proposed Well)******Pad Location: SWSW Section 32, T8S, R17E, S.L.B.&M.*****Notes:**


1. Reclaimed Area to Include Seeding of Approved Vegetation and Sufficient Storm Water Management System.
2. Actual Equipment Layout and Reclaimed Pad Surface Area May Change due to Production Requirements or Site Conditions.

**DISTURBED AREA:****TOTAL DISTURBED AREA = 2.52 ACRES****TOTAL RECLAIMED AREA = 1.82 ACRES****UNRECLAIMED AREA = 0.70 ACRES**

SURVEYED BY: Q.M.	DATE SURVEYED: 11-05-12	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 11-06-12	V2
SCALE: 1" = 60'	REVISED: F.T.M. 12-07-12	

**Tri State** (435) 781-2501  
**Land Surveying, Inc.**  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

**RECEIVED: January 21, 2013**

**NEWFIELD EXPLORATION COMPANY****PROPOSED SITE FACILITY DIAGRAM****2-32-8-17 (Existing Well)****P-32-8-17 (Existing Well) ML-22060****104-5-9-17 (Proposed Well) UTU-020252****128-32-8-17 (Proposed Well) ML-22060***Pad Location: SWSW Section 32, T8S, R17E, S.L.B.&M.  
Duchesne County, Utah***Legend**

Emulsion Line	.....
Load Rack	-----
Water Line	-----
Gas Sales	.....
Oil Line	-----

NOT TO SCALE

SURVEYED BY: Q.M.	DATE SURVEYED: 11-05-12	VERSION:
DRAWN BY: F.T.M.	DATE DRAWN: 11-06-12	V2
SCALE: NONE	REVISED: F.T.M. 12-07-12	

**Tri State** (435) 781-2501  
**Land Surveying, Inc.**  
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: January 21, 2013

NEWFIELD



VIA ELECTRONIC DELIVERY

January 22, 2013

State of Utah, Division of Oil, Gas and Mining  
ATTN: Diana Mason  
P.O. Box 145801  
Salt Lake City, UT 84114-5801

**Newfield Exploration Company**

1001 17th Street | Suite 2000  
Denver, Colorado 80202  
PH 303-893-0102 | FAX 303-893-0103

RE: Directional Drilling  
**GMBU 104-5-9-17**  
Greater Monument Butte (Green River) Unit

Surface Hole: T8S-R17E Section 32: SWSW (ML-22060)  
483' FSL 663' FWL

At Target: T9S-R17E Section 5: Lot 5 (NWNW) (UTU-020252)  
182' FNL 660' FWL

Duchesne County, Utah

Dear Ms. Mason:

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 1/21/2013, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4121 or by email at [lburget@newfield.com](mailto:lburget@newfield.com). Your consideration in this matter is greatly appreciated.

Sincerely,  
Newfield Production Company

Leslie Burget  
Land Associate



Form 3160-3  
(August 2007)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTFORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

## APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU020252
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator NEWFIELD EXPLORATION Contact: MANDIE CROZIER E-Mail: mcrozier@newfield.com		7. If Unit or CA Agreement, Name and No. GREATER MONUMENT
3a. Address ROUTE #3 BOX 3630 MYTON, UT 84052		8. Lease Name and Well No. GMBU 104-5-9-17
3b. Phone No. (include area code) Ph: 435-646-4825 Fx: 435-646-3031		9. API Well No.
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWSW 483FSL 663FWL At proposed prod. zone NWNW Lot 5 182FNL 660FWL		10. Field and Pool, or Exploratory MONUMENT BUTTE
14. Distance in miles and direction from nearest town or post office* 12.0 MILES SE OF MYTON, UT		11. Sec., T., R., M., or Blk. and Survey or Area Sec 32 T8S R17E Mer SLB
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 182'	16. No. of Acres in Lease 320.13	12. County or Parish DUCESNE
17. Spacing Unit dedicated to this well 10.00	13. State UT	
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 842'	19. Proposed Depth 6298 MD 6258 TVD	20. BLM/BIA Bond No. on file WYB000493
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5245 GL	22. Approximate date work will start 03/31/2012	23. Estimated duration 7 DAYS

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- |   |  |
|---|--|
| 1. Well plat certified by a registered surveyor.  | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).    |
| 2. A Drilling Plan.   | 5. Operator certification  |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature (Electronic Submission)	Name (Printed/Typed) MANDIE CROZIER Ph: 435-646-4825	Date 01/21/2013
Title REGULATORY ANALYST		
Approved by (Signature)	Name (Printed/Typed)	Date
Title	Office	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

## Additional Operator Remarks (see next page)

Electronic Submission #187453 verified by the BLM Well Information System  
For NEWFIELD EXPLORATION, sent to the Vernal

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*



API Well Number: 43013519770000

**Additional Operator Remarks:**

SURFACE LEASE: ML-22060  
BOTTOM HOLE LEASE: UTU-020252

**T8S, R17E, S.L.B.&M.**

**NEWFIELD EXPLORATION COMPANY**



- NOTES:**
1. Well footages are measured at right angles to the Section Lines.
  2. Bearings are based on Global Positioning Satellite observations.
  3. The Center of Pattern bears 500°33'56"E 507.62' from the Top of Hole.

◆ = SECTION CORNERS LOCATED

THIS IS TO CERTIFY THAT THE ABOVE SURVEY WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
STACY W. STEWART  
12-07-12  
STATE OF UTAH

**TRI STATE LAND SURVEYING & CONSULTING**  
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
(435) 781-2501


DATE SURVEYED: 11-05-12	SURVEYED BY: Q.M.	VERSION:  
DATE DRAWN: 11-06-12	DRAWN BY: F.T.M.	V2
REVISED: 12-07-12 F.T.M.	SCALE: 1" = 1000'	

<b>NAD 83 (SURFACE LOCATION)</b>
LATITUDE = 40°04'06.47"
LONGITUDE = 110°02'14.95"
<b>NAD 27 (SURFACE LOCATION)</b>
LATITUDE = 40°04'06.60"
LONGITUDE = 110°02'12.42"


BASIS OF ELEV: Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

T9S, R17E, S.L.B.&M.

NEWFIELD EXPLORATION COMPANY



NOTES:  
1. Well footages are measured at right angles to the Section Lines.  
2. Bearings are based on Global Positioning Satellite observations.  
3. The Center of Pattern footages are 25' FNL & 660' FWL.



THIS IS TO CERTIFY THAT THE ABOVE SURVEY WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

RECEIVED  
12-07-12  
STACY W.  
REGISTERED LAND SURVEYOR  
STATE OF UTAH


TRI STATE LAND SURVEYING & CONSULTING  
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078  
(435) 781-2501

DATE SURVEYED: 11-05-12	SURVEYED BY: Q.M.	VERSION: V2
DATE DRAWN: 11-06-12	DRAWN BY: F.T.M.	
REVISED: 12-07-12 F.T.M.	SCALE: 1" = 1000'	

NAD 83 (CENTER OF PATTERN)	NAD 83 (BOTTOM HOLE LOCATION)
LATITUDE = 40°04'01.45"	LATITUDE = 40°03'59.90"
LONGITUDE = 110°02'15.00"	LONGITUDE = 110°02'15.01"
NAD 27 (CENTER OF PATTERN)	NAD 27 (BOTTOM HOLE LOCATION)
LATITUDE = 40°04'01.59"	LATITUDE = 40°04'00.03"
LONGITUDE = 110°02'12.46"	LONGITUDE = 110°02'12.43"

SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:  
3160  
(UT-922)

February 20, 2013

### Memorandum

To: Assistant Field Office Manager Minerals,  
Vernal Field Office

From: Michael Coulthard, Petroleum Engineer

Subject: 2013 Plan of Development Greater Monument  
Butte Unit, Duchesne and Uintah Counties,  
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2013 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-51977	GMBU 104-5-9-17	Sec 32 T08S R17E 0483 FSL 0663 FWL BHL Sec 05 T09S R17E 0182 FNL 0660 FWL
43-013-51978	GMBU 127-36-8-16	Sec 36 T08S R16E 2147 FSL 1819 FWL BHL Sec 36 T08S R16E 1173 FSL 2055 FWL
43-013-51979	GMBU 104-1-9-16	Sec 36 T08S R16E 0724 FSL 0856 FEL BHL Sec 01 T09S R16E 0376 FNL 0575 FWL
43-013-51980	GMBU 111-32-8-17	Sec 32 T08S R17E 0672 FNL 1977 FWL BHL Sec 32 T08S R17E 1463 FNL 1934 FWL
43-013-51981	GMBU 118-3-9-16	Sec 03 T09S R16E 1862 FSL 1919 FEL BHL Sec 03 T09S R16E 2567 FNL 1865 FEL
43-013-51993	GMBU 3-10-9-16	Sec 10 T09S R16E 0814 FNL 2092 FWL
43-013-51994	GMBU 6-30-9-16	Sec 30 T09S R16E 2341 FNL 0398 FWL BHL Sec 30 T09S R16E 1981 FNL 1883 FWL

RECEIVED: February 20, 2013

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-51995	GMBU 5-30-9-16	Sec 30 T09S R16E 2362 FNL 0400 FWL
43-013-51996	GMBU 8-27-9-15	Sec 27 T09S R15E 2132 FNL 0532 FEL
43-013-51997	GMBU 16-32-8-17	Sec 32 T08S R17E 0836 FSL 0587 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard  
DN: cn=Michael L. Coulthard, o=Bureau of Land  
Management, ou=Branch of Minerals,  
email=Michael\_Coulthard@blm.gov, c=US  
Date: 2013.02.20 13:16:01 -07'00'

bcc: File - Greater Monument Butte Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:2-20-13

RECEIVED: February 20, 2013





Project: USGS Myton SW (UT)  
 Site: SECTION 32 T8S, R17E  
 Well: 104-5-9-17  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.13°

Magnetic Field  
 Strength: 52150.4snT  
 Dip Angle: 65.78°  
 Date: 11/8/2012  
 Model: IGRF2010



## WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
104-5-9-17 TGT	4975.0	-507.6	5.0	Circle (Radius: 75.0)

## SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1065.8	6.99	179.43	1064.7	-28.4	0.3	1.50	179.43	28.4	
4	5005.4	6.99	179.43	4975.0	-507.6	5.0	0.00	0.00	507.6	104-5-9-17 TGT
5	6298.0	6.99	179.43	6258.0	-664.8	6.6	0.00	0.00	664.9	



Received: January 21, 2013







Project: USGS Myton SW (UT)  
 Site: SECTION 36 T8S, R16E  
 Well: 127-36-8-16  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.14°

Magnetic Field  
 Strength: 52146.3snT  
 Dip Angle: 65.78°  
 Date: 11/8/2012  
 Model: IGRF2010



#### WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
127-36-8-16 TGT	5121.0	-744.4	192.2	Circle (Radius: 75.0)

#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1296.1	10.44	165.52	1292.2	-61.2	15.8	1.50	165.52	63.2	
4	5189.3	10.44	165.52	5121.0	-744.4	192.2	0.00	0.00	768.8	127-36-8-16 TGT
5	6478.7	10.44	165.52	6389.0	-970.6	250.7	0.00	0.00	1002.5	



Received: January 21, 2013

API Well Number: 43013519770000





Project: USGS Myton SW (UT)  
 Site: SECTION 36 T8S, R16E  
 Well: 104-1-9-16  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.14°

Magnetic Field  
 Strength: 52144.4snT  
 Dip Angle: 65.78°  
 Date: 11/8/2012  
 Model: IGRF2010



#### WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
104-1-9-16 TGT	5040.0	-841.6	-194.0	Circle (Radius: 75.0)

#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1405.3	12.08	192.98	1399.3	-82.4	-19.0	1.50	192.98	84.6	
4	5128.4	12.08	192.98	5040.0	-841.6	-194.0	0.00	0.00	863.7	104-1-9-16 TGT
5	6412.8	12.08	192.98	6296.0	-1103.5	-254.4	0.00	0.00	1132.5	




Received: January 21, 2013

API Well Number: 43013519770000





Project: USGS Myton SW (UT)  
 Site: SECTION 32 T8S, R17E  
 Well: 111-32-8-17  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.13°

Magnetic Field  
 Strength: 52157.5snT  
 Dip Angle: 65.79°  
 Date: 11/8/2012  
 Model: IGRF2010



#### WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
111-32-8-17 TGT	5080.0	-605.4	-23.0	Circle (Radius: 75.0)

#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1146.4	8.20	182.18	1144.5	-39.0	-1.5	1.50	182.18	39.0	
4	5122.5	8.20	182.18	5080.0	-605.4	-23.0	0.00	0.00	605.8	111-32-8-17 TGT
5	6429.8	8.20	182.18	6374.0	-791.6	-30.1	0.00	0.00	792.2	




Received: January 21, 2013

API Well Number: 43013519770000





Project: USGS Myton SW (UT)  
 Site: SECTION 3 T9S, R16E  
 Well: 118-3-9-16  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.15°

Magnetic Field  
 Strength: 52132.7snT  
 Dip Angle: 65.76°  
 Date: 11/8/2012  
 Model: IGRF2010



#### WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
118-3-9-16 TGT	5025.0	674.6	25.7	Circle (Radius: 75.0)

#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1221.3	9.32	2.18	1218.5	50.4	1.9	1.50	2.18	50.4	
4	5078.6	9.32	2.18	5025.0	674.6	25.7	0.00	0.00	675.0	118-3-9-16 TGT
5	6364.6	9.32	2.18	6294.0	882.7	33.6	0.00	0.00	883.3	



Received: January 21, 2013

API Well Number: 43013519770000





Project: USGS Myton SW (UT)  
 Site: SECTION 30 T9S, R16E  
 Well: 6-30-9-16  
 Wellbore: Wellbore #1  
 Design: Design #1



Azimuths to True North  
 Magnetic North: 11.14°

Magnetic Field  
 Strength: 52067.1snT  
 Dip Angle: 65.70°  
 Date: 1/23/2013  
 Model: IGRF2010



#### WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
6-30-9-16 TGT	6000.0	376.1	1479.9	Circle (Radius: 75.0)



#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1774.6	17.62	75.74	1756.2	44.1	173.7	1.50	75.74	179.2	
4	6227.3	17.62	75.74	6000.0	376.1	1479.9	0.00	0.00	1527.0	6-30-9-16 TGT



Received: January 29, 2013

Units	Wells Query
<b>STATUS</b>	<b>Status</b>
ACTIVE	APD - Approved Permit
EXPLORATORY	DRIL - Spudded (Drilling Commenced)
GAF STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERMAL	PQW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
<b>Fields</b>	TA - Temp. Abandoned
<b>STATUS</b>	TW - Test Well
Unknown	WOW - Water Disposal
ABANDONED	WW - Water Injection Well
ACTIVE	WSW - Water Supply Well
COMBINED	Bottom Hole Location - Oil/Gas/D
INACTIVE	
STORAGE	
TERMINATED	



API Well Number : 43013519770000



dianawhitney@utah.gov

Mail

More

4 of about 97

COMPOSE

Inbox (25)

Starred

Important

Sent Mail

Drafts

BLM (83)

Cabinet

Electronic filing

Eng. Tech

New Permits

saved

Follow up

Misc

Priority

Tariq

More

## Newfield Well Approvals

Inbox x



**Jeff Conley**

2:14 PM (16 hours ago)



to Jim, Lavonne, mcrozier, cdmiller, me, Brad

The following wells have been approved by SITLA including arch and paleo resources

(4301351967) GMBU B-21-9-17  
(4301351980) GMBU 111-32-8-17  
(4301351978) GMBU 127-36-8-16  
(4301351976) GMBU 128-32-8-17  
(4301351977) GMBU 104-5-9-17

The following well is approved by SITLA including arch and paleo with 1 arch recommendation

(4301351979) GMBU 104-1-9-16 (U-12-MQ-1092b,s; 1 eligible site, 42Dc2653, adjacent to the north side of the well pad - cultural clearance is given provided the proponent restricts development to the north of the existing well pad; if the proponent decides expansion of the well pad to the north is necessary, then either archaeological monitoring or avoidance fencing along the southern edge of the eligible site is required)

People (6)

**Jeff Conley**

Trust Lands Resource Specialist

[Show details](#)



Click here to [Reply](#), [Reply to all](#), or [Forward](#)

## **ON-SITE PREDRILL EVALUATION**

### **Utah Division of Oil, Gas and Mining**

**Operator** NEWFIELD PRODUCTION COMPANY  
**Well Name** GMBU 104-5-9-17  
**API Number** 43013519770000    **APD No** 7499    **Field/Unit** MONUMENT BUTTE  
**Location: 1/4,1/4** SWSW    **Sec** 32    **Tw** 8.0S    **Rng** 17.0E    483    FSL    663    FWL  
**GPS Coord (UTM)**    **Surface Owner**

#### **Participants**

Shon McKinnon - Newfield

#### **Regional/Local Setting & Topography**

New well on Existing location. Host well is the 2-32-8-17  
Location was not staked and coordiantes could not be verified

#### **Surface Use Plan**

**Current Surface Use**  
Existing Well Pad

<b>New Road Miles</b>	<b>Well Pad</b> <b>Width   Length</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
-----------------------	--	---------------------------	--------------------------

**Ancillary Facilities**

#### **Waste Management Plan Adequate?**

#### **Environmental Parameters**

**Affected Floodplains and/or Wetlands**

**Flora / Fauna**

**Soil Type and Characteristics**

**Erosion Issues**

**Sedimentation Issues**

**Site Stability Issues**

**Drainage Diverson Required?**

**Berm Required?**

**Erosion Sedimentation Control Required?**

<b>Paleo Survey Run?</b>	<b>Paleo Potental Observed?</b>	<b>Cultural Survey Run?</b>	<b>Cultural Resources?</b>
--------------------------	---------------------------------	-----------------------------	----------------------------

#### **Reserve Pit**



**Site-Specific Factors**

**Site Ranking**

**Distance to Groundwater (feet)**  
**Distance to Surface Water (feet)**  
**Dist. Nearest Municipal Well (ft)**  
**Distance to Other Wells (feet)**  
**Native Soil Type**  
**Fluid Type**  
**Drill Cuttings**  
**Annual Precipitation (inches)**  
**Affected Populations**  
**Presence Nearby Utility Conduits**

**Final Score**

**Sensitivity Level**

**Characteristics / Requirements**

**Closed Loop Mud Required?   Liner Required?   Liner Thickness   Pit Underlayment  
Required?**

**Other Observations / Comments**

Chris Jensen  
**Evaluator**

2/13/2013  
**Date / Time**

# Application for Permit to Drill

## Statement of Basis

### Utah Division of Oil, Gas and Mining

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Owner</b>	<b>CBM</b>
7499	43013519770000	SITLA	OW	S	No
<b>Operator</b>	NEWFIELD PRODUCTION COMPANY		<b>Surface Owner-APD</b>		
<b>Well Name</b>	GMBU 104-5-9-17		<b>Unit</b>	GMBU (GRRV)	
<b>Field</b>	MONUMENT BUTTE		<b>Type of Work</b>	DRILL	
<b>Location</b>	SWSW 32 8S 17E S 483 FSL 663 FWL GPS Coord (UTM) 582087E 4435798N				

**Geologic Statement of Basis**

The mineral rights for the proposed well are owned by the Federal Government. The BLM will be the agency responsible for evaluating and approving the drilling, casing and cement programs.

Brad Hill  
**APD Evaluator**

2/26/2013  
**Date / Time**

**Surface Statement of Basis**

New well on Existing location. Host well is the 2-32-8-17. Location was not staked and coordiantes could not be verified. I see no further issues of concern.

Chris Jensen  
**Onsite Evaluator**

2/13/2013  
**Date / Time**

**Conditions of Approval / Application for Permit to Drill**

<b>Category</b>	<b>Condition</b>
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 1/21/2013

API NO. ASSIGNED: 43013519770000

WELL NAME: GMBU 104-5-9-17

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: SWSW 32 080S 170E

Permit Tech Review: ☒

SURFACE: 0483 FSL 0663 FWL

Engineering Review: ☐

BOTTOM: 0182 FNL 0660 FWL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.06844

LONGITUDE: -110.03739

UTM SURF EASTINGS: 582087.00

NORTHINGS: 4435798.00

FIELD NAME: MONUMENT BUTTE

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-020252

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 3 - State

COALBED METHANE: NO

## RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: FEDERAL - WYB000493☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingling Approved

## LOCATION AND SITING:

☐ R649-2-3.

Unit: GMBU (GRRV)

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 213-11

Effective Date: 11/30/2009

Siting: Suspends General Siting

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason  
5 - Statement of Basis - bhill  
15 - Directional - dmason  
27 - Other - bhill

RECEIVED: March 04, 2013



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** GMBU 104-5-9-17

**API Well Number:** 43013519770000

**Lease Number:** UTU-020252

**Surface Owner:** STATE

**Approval Date:** 3/4/2013

### Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

### Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the

following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Pro Petro 8  
Submitted By Branden Arnold Phone Number 435-401-0223  
Well Name/Number GMBU 104-5-9-17  
Qtr/Qtr SW/SW Section 32 Township 8S Range 17E  
Lease Serial Number UTU-020252  
API Number 43-013-51977-00-X1

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 7/25/13 7:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 7/25/13 3:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

**RECEIVED**  
**JUL 24 2013**  
DIV. OF OIL, GAS & MINING

Date/Time \_\_\_\_\_ AM ☐ PM ☐

Remarks \_\_\_\_\_

---

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-020252
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> GMBU (GRRV)
<b>3. ADDRESS OF OPERATOR:</b> Rt 3 Box 3630 , Myton, UT, 84052		<b>8. WELL NAME and NUMBER:</b> GMBU 104-5-9-17
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0483 FSL 0663 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSW Section: 32 Township: 08.0S Range: 17.0E Meridian: S		<b>9. API NUMBER:</b> 43013519770000
<b>PHONE NUMBER:</b> 435 646-4825 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: <b>7/25/2013</b>	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  

MIRU, drill and run 5' of 14" conductor, set at 15'kb. Drill 12 1/4" surface f/ 15 to 329'kb, ran 7 jts 8 5/8. Pumped 200 sx of G neat cement. Returned 6 barrels. Bump plug at 350

**Accepted by the  
Utah Division of  
Oil, Gas and Mining**

**FOR RECORD ONLY**

August 12, 2013

<b>NAME (PLEASE PRINT)</b> Cherei Neilson	<b>PHONE NUMBER</b> 435 646-4883	<b>TITLE</b> Drilling Technician
<b>SIGNATURE</b> N/A	<b>DATE</b> 8/12/2013	

**NEWFIELD****Casing****Conductor**

Legal Well Name GMBU 104-5-9-17			Wellbore Name Original Hole		
API/UWI 43013519770000	Surface Legal Location	Field Name GMBU CTB5	Well Type Exploration	Well Configuration Type Slant	
Well RC 500352123	County Duchesne	State/Province Utah	Spud Date	Rig Release Date	

<b>Wellbore</b>					
Wellbore Name			Kick Off Depth (ftKB)		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date

<b>Wellhead</b>			
Type	Install Date	Service	Comment

<b>Wellhead Components</b>				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description	Set Depth (ftKB)	Run Date	Set Tension (kips)
Conductor	15	7/29/2013	
Centralizers		Scratchers	

<b>Casing Components</b>												
Item Des	OD (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)	ID (in)
Casing Joint	14	36.75	H-40		1	5.00	10.0	15.0				13.500



**NEWFIELD****Casing****Surface**

Legal Well Name GMBU 104-5-9-17			Wellbore Name Original Hole		
API/UWI 43013519770000	Surface Legal Location	Field Name GMBU CTB5		Well Type Exploration	Well Configuration Type Slant
Well RC 500352123	County Duchesne	State/Province Utah		Spud Date	Rig Release Date

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB)		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	10	15	7/29/2013	7/29/2013
Vertical	12 1/4	15	329	7/29/2013	7/29/2013


Wellhead				
Type	Install Date	Service	Comment	

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description	Set Depth (ftKB)	Run Date	Set Tension (kips)
Surface	322	7/29/2013	
Centralizers	Scratchers		

Casing Components												
Item Des	OD (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)	ID (in)
Cut off	8 5/8	24.00	J-55		1	42.81	9.8	52.6				8.097
Casing Joints	8 5/8	24.00	J-55		5	222.30	52.6	274.9				8.097
Float Collar	8 5/8	24.00	J-55		1	0.92	274.9	275.8				8.097
Shoe Joint	8 5/8	24.00	J-55		1	44.78	275.8	320.6				8.097
Guide Shoe	8 5/8	24.00	J-55		1	1.39	320.6	322.0				8.097

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT



FORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU020252
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator NEWFIELD EXPLORATION COMPANY Contact: MANDIE CROZIER Email: mcrozier@newfield.com		7. If Unit or CA Agreement, Name and No. UTU87538X
3a. Address ROUTE 3 BOX 3630 MYTON, UT 84052	3b. Phone No. (include area code) Ph: 435.646.3721 Ext: 4825 Fx: 435.646.3031	8. Lease Name and Well No. GMBU 104-5-9-17
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWSW 483FSL 663FWL At proposed prod. zone Lot 5 182FNL 660FWL <i>Sec 32 T8S R17E</i>		9. API Well No. <i>43-013-51977</i>
14. Distance in miles and direction from nearest town or post office* 12.0 MILES SE OF MYTON, UT		10. Field and Pool, or Exploratory MONUMENT BUTTE
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 182'	16. No. of Acres in Lease 320.13	11. Sec., T., R., M., or Blk. and Survey or Area Sec 32 T8S R17E Mer SLB SME: STATE
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 842'	19. Proposed Depth 6298 MD 6258 TVD	12. County or Parish DUCESNE
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5245 GL	22. Approximate date work will start 03/31/2012	13. State UT
		17. Spacing Unit dedicated to this well 10.00
		20. BLM/BIA Bond No. on file WYB000493
		23. Estimated duration 7 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) MANDIE CROZIER Ph: 435.646.3721 Ext: 4825	Date 01/21/2013
Title REGULATORY TECH.		
Approved by (Signature) <i>[Signature]</i>	Name (Printed/Typed) Jerry Kenczka	Date JUL 17 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #187453 verified by the BLM Well Information System  
For NEWFIELD EXPLORATION COMPANY, sent to the Vernal  
Committed to AFMSS for processing by ROBIN R. HANSEN on 01/25/2013 (13RRH6283AE)

DIV. OF OIL, GAS & MINING

NOTICE OF APPROVAL

\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\*

**Additional Operator Remarks:**

SURFACE LEASE: ML-22060

BOTTOM HOLE LEASE: UTU-020252

**Additional Operator Remarks:**

SURFACE LEASE: ML-22060  
BOTTOM HOLE LEASE: UTU-020252

## Revisions to Operator-Submitted EC Data for APD #187453

	Operator Submitted	BLM Revised (AFMSS)
Lease:	UTU020252	UTU020252
Agreement:	GREATER MONUMENT	UTU87538X (UTU87538X)
Operator:	NEWFIELD EXPLORATION ROUTE #3 BOX 3630 MYTON, UT 84052 Ph: 435-646-3721	NEWFIELD EXPLORATION COMPANY ROUTE 3 BOX 3630 MYTON, UT 84052 Ph: 435.646.3721 Fx: 435.646.3031
Admin Contact:	MANDIE CROZIER REGULATORY ANALYST ROUTE #3 BOX 3630 MYTON, UT 84052 Ph: 435-646-4825 Fx: 435-646-3031 Cell: 435-401-8335 E-Mail: mcrozier@newfield.com	MANDIE CROZIER REGULATORY TECH. ROUTE 3 BOX 3630 MYTON, UT 84052 Ph: 435.646.3721 Ext: 4825 Fx: 435.646.3031 E-Mail: mcrozier@newfield.com
Tech Contact:	MANDIE CROZIER REGULATORY ANALYST ROUTE #3 BOX 3630 MYTON, UT 84052	MANDIE CROZIER REGULATORY TECH. ROUTE 3 BOX 3630 MYTON, UT 84052
Well Name: Number:	GMBU 104-5-9-17	GMBU 104-5-9-17
Location: State: County: S/T/R: Surf Loc:	UT DUCHESNE Sec 32 T8S R17E Mer SLB SWSW 483FSL 663FWL	UT DUCHESNE Sec 32 T8S R17E Mer SLB SWSW 483FSL 663FWL
Field/Pool:	MONUMENT BUTTE	MONUMENT BUTTE
Bond:	WYB000493	WYB000493




UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

Company:	Newfield Exploration Company	Location:	SWSW SEC 32 T8S R17E
Well No:	GMBU 104-5-9-17	Lease No:	UTU020252
API No:	43-013-51977	Agreement:	GMBU

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:blm_ut_vn_opreport@blm.gov">blm_ut_vn_opreport@blm.gov</a> .
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

**STANDARD STIPULATIONS**

**Green River District Reclamation Guidelines**

The Operator will comply with the requirements of the ***Green River District (GRD) Reclamation Guidelines*** formalized by Green River District Instructional Memo UTG000-2011-003 on March 28, 2011. Documentation of the compliance will be as follows:

- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) that designates the proposed site-specific monitoring and reference sites chosen for the location. A description of the proposed sites shall be included, as well as a map showing the locations of the proposed sites.
- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) 3 growing seasons after reclamation efforts have occurred evaluating the status of the reclaimed areas in order to determine whether the BLM standards set forth in the GRD Reclamation Guidelines have been met (30% or greater basal cover).
- Prior to beginning new surface disturbance, the operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) providing the results of the noxious weed inventory described in the GRD Reclamation Guidelines (2011). If weeds are found the report shall include 1) A GPS location recorded in North American Datum 1983; 2) species; 3) canopy cover or number of plants; 4) and size of infestation (estimate square feet or acres. Information shall be also documented in the reclamation report.

**CONDITIONS OF APPROVAL**

**Wildlife**

**In accordance with the Record of Decision for the Castle Peak and Eightmile Flat Oil and Gas Expansion Project, Newfield Rocky Mountains Inc., the following COA's are required:**

- WFM-1 On level or gently sloping ground (5 percent slope or less) Newfield will elevate surface pipelines (4 inches or greater in diameter) a minimum of 6 inches above the ground to allow

passage of small animals beneath the pipe. This ground clearance will be achieved by placing the pipeline on blocks at intervals of 150 to 200 feet.

- WFM-4 Newfield will install noise reduction devices on all pump jacks to reduce intermittent noise to 45 dBA at 660 feet from the source.

#### **For protection of T&E Fish if drawing water from the Green River**

- For areas of fresh water collection, an infiltration gallery will be constructed in a Service approved location. An infiltration gallery is basically a pit or trench dug within the floodplain to a depth below the water table. Water is drawn from the pit rather than from the river directly. If this is not possible, limit pumping within the river to off-channel locations that do not connect to the river during high spring flows.
- If water cannot be drawn using the measures above and the pump head will be located in the river channel where larval fish are known to occur, the following measures apply:
  - Avoid pumping from low-flow or no-flow areas as these habitats tend to concentrate larval fish
  - Avoid pumping to the greatest extent possible, during that period of the year when larval fish may be present (see previous bullet); and
  - Avoid pumping, to the greatest extent possible, during the midnight hours (10:00 p.m. to 2:00 a.m.) as larval drift studies indicate that this is a period of greatest daily activity. Dusk is the preferred pumping time, as larval drift abundance is lowest during this time.
  - Screen all pump intakes with 3/32-inch mesh material.
- Report any fish impinged on the intake screen to the FWS office (801.975.3330) and the:  
Utah Division of Wildlife Resources  
Northeastern Region  
152 East 100 North  
Vernal, UT 84078  
(435) 781-9453

#### **Air Quality**

1. All internal combustion equipment will be kept in good working order.
2. Water or other approved dust suppressants will be used at construction sites and along roads, as determined appropriate by the Authorized Officer. Dust suppressant such as magnesium chloride or fresh water may be used, as needed, during the drilling phase.
3. Open burning of garbage or refuse will not occur at well sites or other facilities.
4. Drill rigs will be equipped with Tier II or better diesel engines.
5. Low bleed pneumatics will be installed on separator dump valves and other controllers.
6. During completion, no venting will occur, and flaring will be limited as much as possible. Production equipment and gathering lines will be installed as soon as possible.
7. Telemetry will be installed to remotely monitor and control production.



8. When feasible, two or more rigs (including drilling and completion rigs) will not be run simultaneously within 200 meters of each other. If two or more rigs must be run simultaneously within 200 meters of each other, then effective public health buffer zones out to 200 meters (m) from the nearest emission source will be implemented. Examples of an effective public health protection buffer zone include the demarcation of a public access exclusion zone by signage at intervals of every 250 feet that is visible from a distance of 125 feet during daylight hours, and a physical buffer such as active surveillance to ensure the property is not accessible by the public during drilling operations. Alternatively, the proponent may demonstrate compliance with the 1-hour NO<sub>2</sub> National Ambient Air Quality Standards (NAAQS) with appropriate and accepted near-field modeling. As part of this demonstration, the proponent may propose alternative mitigation that could include but is not limited to natural gas-fired drill rigs, installation of NO<sub>x</sub> controls, time/use restrictions, and/or drill rig spacing.
9. Green completions will be used for all well completion activities where technically feasible.
10. Employ enhanced VOC emission controls with 95% control efficiency on production equipment having a potential to emit greater than 5 tons per year.

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

Newfield Production Co. shall adhere to all referenced requirements in the SOP (version: "Greater Monument Butte Green River Development Program", Feb 16, 2012). The operator shall also comply with applicable laws and regulations; with lease terms Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the, authorized officer.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.

- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well by CD (compact disc). This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

#### **OPERATING REQUIREMENT REMINDERS:**


- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼¼, Sec., Twn, Rng, and P.M.).

- Date well was placed in a producing status (date of first production for which royalty will be paid).
- The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
- The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
- Unit agreement and/or participating area name and number, if applicable.
- Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.

- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT



FORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU020252
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator NEWFIELD EXPLORATION COMPANY Contact: MANDIE CROZIER Email: mcrozier@newfield.com		7. If Unit or CA Agreement, Name and No. UTU87538X
3a. Address ROUTE 3 BOX 3630 MYTON, UT 84052	3b. Phone No. (include area code) Ph: 435.646.3721 Ext: 4825 Fx: 435.646.3031	8. Lease Name and Well No. GMBU 104-5-9-17
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWSW 483FSL 663FWL At proposed prod. zone Lot 5 182FNL 660FWL <i>Sec 32 T8S R17E</i>		9. API Well No. <i>43-013-51977</i>
14. Distance in miles and direction from nearest town or post office* 12.0 MILES SE OF MYTON, UT		10. Field and Pool, or Exploratory MONUMENT BUTTE
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 182'	16. No. of Acres in Lease 320.13	11. Sec., T., R., M., or Blk. and Survey or Area Sec 32 T8S R17E Mer SLB SME: STATE
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 842'	19. Proposed Depth 6298 MD 6258 TVD	12. County or Parish DUCESNE
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5245 GL	22. Approximate date work will start 03/31/2012	13. State UT
		17. Spacing Unit dedicated to this well 10.00
		20. BLM/BIA Bond No. on file WYB000493
		23. Estimated duration 7 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) MANDIE CROZIER Ph: 435.646.3721 Ext: 4825	Date 01/21/2013
Title REGULATORY TECH.		
Approved by (Signature) <i>[Signature]</i>	Name (Printed/Typed) Jerry Kenczka	Date JUL 17 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #187453 verified by the BLM Well Information System  
For NEWFIELD EXPLORATION COMPANY, sent to the Vernal  
Committed to AFMSS for processing by ROBIN R. HANSEN on 01/25/2013 (13RRH6283AE)

NOTICE OF APPROVAL

\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\*

**Additional Operator Remarks:**

SURFACE LEASE: ML-22060

BOTTOM HOLE LEASE: UTU-020252

**Additional Operator Remarks:**

SURFACE LEASE: ML-22060  
BOTTOM HOLE LEASE: UTU-020252

## Revisions to Operator-Submitted EC Data for APD #187453

	Operator Submitted	BLM Revised (AFMSS)
Lease:	UTU020252	UTU020252
Agreement:	GREATER MONUMENT	UTU87538X (UTU87538X)
Operator:	NEWFIELD EXPLORATION ROUTE #3 BOX 3630 MYTON, UT 84052 Ph: 435-646-3721	NEWFIELD EXPLORATION COMPANY ROUTE 3 BOX 3630 MYTON, UT 84052 Ph: 435.646.3721 Fx: 435.646.3031
Admin Contact:	MANDIE CROZIER REGULATORY ANALYST ROUTE #3 BOX 3630 MYTON, UT 84052 Ph: 435-646-4825 Fx: 435-646-3031 Cell: 435-401-8335 E-Mail: mcrozier@newfield.com	MANDIE CROZIER REGULATORY TECH. ROUTE 3 BOX 3630 MYTON, UT 84052 Ph: 435.646.3721 Ext: 4825 Fx: 435.646.3031 E-Mail: mcrozier@newfield.com
Tech Contact:	MANDIE CROZIER REGULATORY ANALYST ROUTE #3 BOX 3630 MYTON, UT 84052	MANDIE CROZIER REGULATORY TECH. ROUTE 3 BOX 3630 MYTON, UT 84052
Well Name: Number:	GMBU 104-5-9-17	GMBU 104-5-9-17
Location: State: County: S/T/R: Surf Loc:	UT DUCHESNE Sec 32 T8S R17E Mer SLB SWSW 483FSL 663FWL	UT DUCHESNE Sec 32 T8S R17E Mer SLB SWSW 483FSL 663FWL
Field/Pool:	MONUMENT BUTTE	MONUMENT BUTTE
Bond:	WYB000493	WYB000493




UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

Company:	Newfield Exploration Company	Location:	SWSW SEC 32 T8S R17E
Well No:	GMBU 104-5-9-17	Lease No:	UTU020252
API No:	43-013-51977	Agreement:	GMBU

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:blm_ut_vn_opreport@blm.gov">blm_ut_vn_opreport@blm.gov</a> .
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

**STANDARD STIPULATIONS**

**Green River District Reclamation Guidelines**

The Operator will comply with the requirements of the ***Green River District (GRD) Reclamation Guidelines*** formalized by Green River District Instructional Memo UTG000-2011-003 on March 28, 2011. Documentation of the compliance will be as follows:

- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) that designates the proposed site-specific monitoring and reference sites chosen for the location. A description of the proposed sites shall be included, as well as a map showing the locations of the proposed sites.
- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) 3 growing seasons after reclamation efforts have occurred evaluating the status of the reclaimed areas in order to determine whether the BLM standards set forth in the GRD Reclamation Guidelines have been met (30% or greater basal cover).
- Prior to beginning new surface disturbance, the operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) providing the results of the noxious weed inventory described in the GRD Reclamation Guidelines (2011). If weeds are found the report shall include 1) A GPS location recorded in North American Datum 1983; 2) species; 3) canopy cover or number of plants; 4) and size of infestation (estimate square feet or acres. Information shall be also documented in the reclamation report.

**CONDITIONS OF APPROVAL**

**Wildlife**

**In accordance with the Record of Decision for the Castle Peak and Eightmile Flat Oil and Gas Expansion Project, Newfield Rocky Mountains Inc., the following COA's are required:**

- WFM-1 On level or gently sloping ground (5 percent slope or less) Newfield will elevate surface pipelines (4 inches or greater in diameter) a minimum of 6 inches above the ground to allow



passage of small animals beneath the pipe. This ground clearance will be achieved by placing the pipeline on blocks at intervals of 150 to 200 feet.

- WFM-4 Newfield will install noise reduction devices on all pump jacks to reduce intermittent noise to 45 dBA at 660 feet from the source.

#### **For protection of T&E Fish if drawing water from the Green River**

- For areas of fresh water collection, an infiltration gallery will be constructed in a Service approved location. An infiltration gallery is basically a pit or trench dug within the floodplain to a depth below the water table. Water is drawn from the pit rather than from the river directly. If this is not possible, limit pumping within the river to off-channel locations that do not connect to the river during high spring flows.
- If water cannot be drawn using the measures above and the pump head will be located in the river channel where larval fish are known to occur, the following measures apply:
  - Avoid pumping from low-flow or no-flow areas as these habitats tend to concentrate larval fish
  - Avoid pumping to the greatest extent possible, during that period of the year when larval fish may be present (see previous bullet); and
  - Avoid pumping, to the greatest extent possible, during the midnight hours (10:00 p.m. to 2:00 a.m.) as larval drift studies indicate that this is a period of greatest daily activity. Dusk is the preferred pumping time, as larval drift abundance is lowest during this time.
  - Screen all pump intakes with 3/32-inch mesh material.
- Report any fish impinged on the intake screen to the FWS office (801.975.3330) and the:  
Utah Division of Wildlife Resources  
Northeastern Region  
152 East 100 North  
Vernal, UT 84078  
(435) 781-9453

#### **Air Quality**

1. All internal combustion equipment will be kept in good working order.
2. Water or other approved dust suppressants will be used at construction sites and along roads, as determined appropriate by the Authorized Officer. Dust suppressant such as magnesium chloride or fresh water may be used, as needed, during the drilling phase.
3. Open burning of garbage or refuse will not occur at well sites or other facilities.
4. Drill rigs will be equipped with Tier II or better diesel engines.
5. Low bleed pneumatics will be installed on separator dump valves and other controllers.
6. During completion, no venting will occur, and flaring will be limited as much as possible. Production equipment and gathering lines will be installed as soon as possible.
7. Telemetry will be installed to remotely monitor and control production.

8. When feasible, two or more rigs (including drilling and completion rigs) will not be run simultaneously within 200 meters of each other. If two or more rigs must be run simultaneously within 200 meters of each other, then effective public health buffer zones out to 200 meters (m) from the nearest emission source will be implemented. Examples of an effective public health protection buffer zone include the demarcation of a public access exclusion zone by signage at intervals of every 250 feet that is visible from a distance of 125 feet during daylight hours, and a physical buffer such as active surveillance to ensure the property is not accessible by the public during drilling operations. Alternatively, the proponent may demonstrate compliance with the 1-hour NO<sub>2</sub> National Ambient Air Quality Standards (NAAQS) with appropriate and accepted near-field modeling. As part of this demonstration, the proponent may propose alternative mitigation that could include but is not limited to natural gas-fired drill rigs, installation of NO<sub>x</sub> controls, time/use restrictions, and/or drill rig spacing.
9. Green completions will be used for all well completion activities where technically feasible.
10. Employ enhanced VOC emission controls with 95% control efficiency on production equipment having a potential to emit greater than 5 tons per year.

**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

Newfield Production Co. shall adhere to all referenced requirements in the SOP (version: "Greater Monument Butte Green River Development Program", Feb 16, 2012). The operator shall also comply with applicable laws and regulations; with lease terms Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the, authorized officer.

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.

- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well by CD (compact disc). This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

#### **OPERATING REQUIREMENT REMINDERS:**

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
  - Operator name, address, and telephone number.
  - Well name and number.
  - Well location (¼¼, Sec., Twn, Rng, and P.M.).

- Date well was placed in a producing status (date of first production for which royalty will be paid).
- The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
- The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
- Unit agreement and/or participating area name and number, if applicable.
- Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.

- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.



BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# NDSI SS # 2  
Submitted By Jim Smith Phone Number 823-2072  
Well Name/Number GMBU 104-5-9-1785,  
Qtr/Qtr SW/SW Section 32 Township 9S Range 17E  
Lease Serial Number UTU- 020252  
API Number 43-013-51977-00-X1

TD Notice – TD is the final drilling depth of hole.

Date/Time 8/15/13      2:00 AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 8/18/13      6:00 AM ☐ PM ☐

**RECEIVED**

**AUG 14 2013**

**DIV. OF OIL, GAS & MINING**

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# NDSI SS # 2  
Submitted By Jim Smith Phone Number 435-823-2072  
Well Name/Number GMBU 104-5-9-17  
Qtr/Qtr SW/SW Section 32 Township 8S Range 17E  
Lease Serial Number UTU- 020252  
API Number 43-013-51977-00-X1

Rig Move Notice – Move drilling rig to new location.

Date/Time 8/12/13 6:00 AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time 8/12/2013 11:00 AM ☐ PM ☐

Remarks \_\_\_\_\_

---

**RECEIVED**

**AUG 11 2013**

**DIV. OF OIL, GAS & MINING**

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-020252
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> NEWFIELD PRODUCTION COMPANY		<b>7. UNIT or CA AGREEMENT NAME:</b> GMBU (GRRV)
<b>3. ADDRESS OF OPERATOR:</b> Rt 3 Box 3630 , Myton, UT, 84052		<b>8. WELL NAME and NUMBER:</b> GMBU 104-5-9-17
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 0483 FSL 0663 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: SWSW Section: 32 Township: 08.0S Range: 17.0E Meridian: S		<b>9. API NUMBER:</b> 43013519770000
<b>PHONE NUMBER:</b> 435 646-4825 Ext		<b>9. FIELD and POOL or WILDCAT:</b> MONUMENT BUTTE
<b>COUNTY:</b> DUCHESNE		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 9/20/2013	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="text-align: center;">           The above well was placed on production on 09/20/2013 at 16:30 hours.         </div> <div style="text-align: right; margin-top: 20px;"> <b>Accepted by the            Utah Division of            Oil, Gas and Mining            FOR RECORD ONLY            October 08, 2013</b> </div>		
<b>NAME (PLEASE PRINT)</b> Jennifer Peatross	<b>PHONE NUMBER</b> 435 646-4885	<b>TITLE</b> Production Technician
<b>SIGNATURE</b> N/A	<b>DATE</b> 10/7/2013	

Form 3160-4  
(March 2012)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0137  
Expires: October 31, 2014

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Reserv., Other: _____										6. If Indian, Allottee or Tribe Name _____ 7. Unit or CA Agreement Name and No. <b>GMBU (GRRV)</b> 8. Lease Name and Well No. <b>GMBU 104-5-9-17</b> 9. API Well No. <b>43-013-51977</b>																													
2. Name of Operator <b>NEWFIELD PRODUCTION COMPANY</b>										10. Field and Pool or Exploratory <b>MONUMENT BUTTE</b> 11. Sec., T., R., M., on Block and Survey or Area Sec 32 T8S, R17E, Mer: SLB																													
3. Address <b>ROUTE #3 BOX 3630 MYTON, UT 84052</b>										3a. Phone No. (include area code) <b>Ph:435-646-3721</b>																													
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface <b>483' FSL 663' FWL (SE/SE) SEC 32, T8S, R17E (ML-22060)</b> At top prod. interval reported below <b>47' FSL 655' FWL (SE/SE) SEC 32, T8S, R17E (ML-22060)</b> At total depth <b>188' FNL 652' FWL (NW/NW) SEC 5, T9S, R17E (UTU020252)</b>																				12. County or Parish <b>DUCHESNE</b>										13. State <b>UT</b>									
14. Date Spudded <b>07/25/2013</b>										15. Date T.D. Reached <b>08/19/2013</b>										16. Date Completed <b>09/29/2013</b> <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.										17. Elevations (DF, RKB, RT, GL)* <b>5245' GL 5255' KB</b>									
18. Total Depth: MD <b>6227'</b> TVD <b>6185'</b>										19. Plug Back T.D.: MD <b>6194'</b> TVD _____										20. Depth Bridge Plug Set: MD _____ TVD _____																			
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) <b>DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND</b>															22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy)																								
23. Casing and Liner Record (Report all strings set in well)																																							
Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled																														
12-1/4"	8-5/8" J-55	24#	0	322'		200 CLASS G																																	
7-7/8"	5-1/2" J-55	15.5#	0	6218'		260 Econocem		32'																															
						460Expandacem																																	
24. Tubing Record																																							
Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)																												
2-7/8"	EOT@6030'	TA@5843'																																					
25. Producing Intervals										26. Perforation Record																													
Formation			Top		Bottom		Perforated Interval			Size		No. Holes		Perf. Status																									
A) Green River			4283'		5874'		4283' - 5874' MD			.34		40																											
B)																																							
C)																																							
D)																																							
27. Acid, Fracture, Treatment, Cement Squeeze, etc.																																							
Depth Interval				Amount and Type of Material																																			
4283' - 5874' MD				Frac w/ 232090#s of 20/40 white sand in 2325 bbls of Lightning 17 fluid, in 5 stages.																																			
28. Production - Interval A																																							
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method																														
9/20/13	9/30/13	24	➡	65	1	36			2.5 X 1.75 X 20 RHAC																														
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status																															
			➡					PRODUCING																															
28a. Production - Interval B																																							
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method																														
			➡																																				
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status																															
			➡																																				

\*(See instructions and spaces for additional data on page 2)

RECEIVED: Oct. 15, 2013

28b. Production - Interval C									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

## 30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers  
GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MARK GARDEN GULCH 1	3787' 3980'
				GARDEN GULCH 2 POINT 3	4092' 4369'
				X MRKR Y MRKR	4606' 4643'
				DOUGLAS CREEK MRK BI CARBONATE MRK	4769' 5012'
				B LIMESTONE MRK CASTLE PEAK	5144' 5627'
				BASAL CARBONATE WASATCH	6050' 6168'

## 32. Additional remarks (include plugging procedure):

## 33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)     
 ☐ Geologic Report     
 ☐ DST Report     
 ☒ Directional Survey  
☐ Sundry Notice for plugging and cement verification     
 ☐ Core Analysis     
 ☒ Other: Drilling daily activity

## 34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)\*

Name (please print) Heather CalderTitle Regulatory TechnicianSignature Heather CalderDate 10/10/2013

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)



## **NEWFIELD EXPLORATION**

**USGS Myton SW (UT)  
SECTION 32 T8S, R17E  
104-5-9-17  
Wellbore #1**

**Design: Actual**

## **End of Well Report**

**19 August, 2013**







## Payzone Directional

### End of Well Report



<b>Company:</b> NEWFIELD EXPLORATION <b>Project:</b> USGS Myton SW (UT) <b>Site:</b> SECTION 32 T8S, R17E <b>Well:</b> 104-5-9-17 <b>Wellbore:</b> Wellbore #1 <b>Design:</b> Actual		<b>Local Co-ordinate Reference:</b> Well 104-5-9-17 104-5-9-17 @ 5255.0ft (NDSI SS #2) 104-5-9-17 @ 5255.0ft (NDSI SS #2) True Minimum Curvature EDM 2003 21 Single User Db	
<b>Project:</b> USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA <b>Map System:</b> US State Plane 1983 <b>Geo Datum:</b> North American Datum 1983 <b>Map Zone:</b> Utah Central Zone		<b>System Datum:</b> Mean Sea Level	
<b>Site</b> SECTION 32 T8S, R17E, SEC 32 T8S, R17E			
<b>Site Position:</b> From: Lat/Long Position Uncertainty: 0.0 ft		Northing: 7,197,024.42 ft Easting: 2,049,704.59 ft Slot Radius: Latitude: 40° 4' 6.630 N Longitude: 110° 2' 14.800 W Grid Convergence: 0.94°	
<b>Well</b> 104-5-9-17, SHL LAT: 40 04 06.47 LONG: -110 02 14.95			
Well Position +N/-S 0.0 ft +E/-W 0.0 ft Position Uncertainty 0.0 ft		Northing: 7,197,008.03 ft Easting: 2,049,693.19 ft Wellhead Elevation: 5,255.0 ft Latitude: 40° 4' 6.470 N Longitude: 110° 2' 14.950 W Ground Level: 5,245.0 ft	
<b>Wellbore</b> Wellbore #1			
<b>Magnetics</b> Model Name Sample Date Declination (°) Dip Angle (°) Field Strength (nT) IGRF2010 11/8/2012 11.13 65.78 52,150			
<b>Design</b> Actual			
<b>Audit Notes:</b>			
Version: 1.0 Phase: ACTUAL Tie On Depth: 0.0			
Vertical Section: Depth From (TVD) (ft) +N/-S (ft) +E/-W (ft) Direction (°) 0.0 0.0 0.0 179.10			
<b>Survey Program</b> Date 8/19/2013			
From (ft) To (ft) Survey (Wellbore) Tool Name Description 377.0 6,227.0 Survey #1 (Wellbore #1) MWD MWD - Standard			



## Payzone Directional

### End of Well Report



**Company:** NEWFIELD EXPLORATION  
**Project:** USGS Myton SW (UT)  
**Site:** SECTION 32 T8S, R17E  
**Well:** 104-5-9-17  
**Wellbore:** Wellbore #1  
**Design:** Actual

**Local Co-ordinate Reference:** Well 104-5-9-17  
**TVD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**MD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature  
**Database:** EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	0.0	0.00	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00
	377.0	0.60	207.90	377.0	1.7	-1.7	-0.9	0.16	0.16	0.00
	407.0	0.40	176.20	407.0	2.0	-2.0	-1.0	1.11	-0.67	-105.67
	437.0	0.60	217.70	437.0	2.2	-2.2	-1.1	1.34	0.67	138.33
	468.0	0.40	251.70	468.0	2.4	-2.4	-1.3	1.13	-0.65	109.68
	498.0	0.20	172.30	498.0	2.4	-2.5	-1.4	1.38	-0.67	-264.67
	528.0	0.40	246.30	528.0	2.5	-2.6	-1.5	1.32	0.67	246.67
	559.0	0.80	220.30	559.0	2.7	-2.8	-1.7	1.53	1.29	-83.87
	588.0	0.80	196.10	588.0	3.1	-3.1	-1.9	1.16	0.00	-83.45
	618.0	1.20	192.10	618.0	3.6	-3.6	-2.0	1.35	1.33	-13.33
	648.0	1.70	193.60	648.0	4.3	-4.4	-2.2	1.67	1.67	5.00
	679.0	1.80	189.00	679.0	5.3	-5.3	-2.4	0.56	0.32	-14.84
	709.0	2.00	189.00	708.9	6.2	-6.3	-2.5	0.67	0.67	0.00
	739.0	1.80	180.60	738.9	7.2	-7.3	-2.6	1.14	-0.67	-28.00
	770.0	2.20	184.80	769.9	8.3	-8.3	-2.7	1.37	1.29	13.55
	800.0	2.50	175.70	799.9	9.5	-9.6	-2.7	1.59	1.00	-30.33
	830.0	3.30	185.90	829.8	11.0	-11.1	-2.7	3.16	2.67	34.00
	861.0	3.40	182.30	860.8	12.8	-12.9	-2.8	0.75	0.32	-11.61
	891.0	4.00	176.30	890.7	14.8	-14.8	-2.8	2.38	2.00	-20.00
	922.0	4.70	176.20	921.6	17.1	-17.2	-2.6	2.26	2.26	-0.32
	952.0	5.10	184.60	951.5	19.7	-19.7	-2.7	2.73	1.33	28.00
	982.0	5.60	178.60	981.4	22.5	-22.5	-2.7	2.50	1.67	-20.00
	1,013.0	6.40	184.30	1,012.2	25.7	-25.7	-2.8	3.21	2.58	18.39
	1,057.0	7.30	178.90	1,055.9	30.9	-31.0	-3.0	2.51	2.05	-12.27
	1,100.0	7.90	185.10	1,098.5	36.6	-36.7	-3.2	2.36	1.40	14.42
	1,144.0	8.10	184.70	1,142.1	42.7	-42.8	-3.7	0.47	0.45	-0.91
	1,188.0	8.60	180.30	1,185.6	49.1	-49.1	-4.0	1.84	1.14	-10.00



# Payzone Directional

## End of Well Report



**Company:** NEWFIELD EXPLORATION  
**Project:** USGS Myton SW (UT)  
**Site:** SECTION 32 T8S, R17E  
**Well:** 104-5-9-17  
**Wellbore:** Wellbore #1  
**Design:** Actual

**Local Co-ordinate Reference:** Well 104-5-9-17  
**TVD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**MD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature  
**Database:** EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	1,232.0	8.50	179.30	1,229.2	55.6	-55.7	-3.9	0.41	-0.23	-2.27
	1,276.0	8.70	184.20	1,272.7	62.2	-62.3	-4.2	1.73	0.45	11.14
	1,319.0	8.70	179.80	1,315.2	68.7	-68.8	-4.4	1.55	0.00	-10.23
	1,363.0	8.60	177.30	1,358.7	75.3	-75.4	-4.2	0.88	-0.23	-5.68
	1,407.0	8.30	180.80	1,402.2	81.8	-81.8	-4.1	1.35	-0.68	7.95
	1,451.0	8.70	180.20	1,445.7	88.3	-88.3	-4.2	0.93	0.91	-1.36
	1,494.0	8.70	175.10	1,488.2	94.7	-94.8	-3.9	1.79	0.00	-11.86
	1,538.0	8.30	173.50	1,531.7	101.2	-101.3	-3.2	1.06	-0.91	-3.64
	1,582.0	8.15	175.40	1,575.3	107.5	-107.6	-2.6	0.71	-0.34	4.32
	1,626.0	8.75	172.00	1,618.8	113.9	-114.0	-1.9	1.77	1.36	-7.73
	1,670.0	8.80	171.20	1,662.3	120.6	-120.6	-0.9	0.30	0.11	-1.82
	1,714.0	8.70	169.40	1,705.8	127.2	-127.2	0.2	0.66	-0.23	-4.09
	1,757.0	8.40	172.80	1,748.3	133.5	-133.5	1.2	1.37	-0.70	7.91
	1,801.0	8.10	168.00	1,791.8	139.8	-139.8	2.2	1.71	-0.68	-10.91
	1,845.0	7.45	170.40	1,835.4	145.6	-145.6	3.3	1.65	-1.48	5.45
	1,889.0	7.30	173.00	1,879.1	151.2	-151.2	4.2	0.83	-0.34	5.91
	1,933.0	7.00	174.70	1,922.7	156.7	-156.6	4.8	0.83	-0.68	3.86
	1,976.0	6.90	173.45	1,965.4	161.9	-161.8	5.3	0.42	-0.23	-2.91
	2,020.0	7.40	177.05	2,009.1	167.3	-167.3	5.7	1.53	1.14	8.18
	2,064.0	7.16	173.70	2,052.7	172.9	-172.8	6.2	1.11	-0.55	-7.61
	2,108.0	6.80	180.10	2,096.4	178.2	-178.1	6.5	1.95	-0.82	14.55
	2,152.0	6.80	182.60	2,140.1	183.4	-183.4	6.4	0.67	0.00	5.68
	2,195.0	6.50	177.40	2,182.8	188.4	-188.3	6.3	1.56	-0.70	-12.09
	2,239.0	6.70	183.10	2,226.5	193.5	-193.4	6.3	1.56	0.45	12.95
	2,283.0	6.50	178.50	2,270.2	198.5	-198.4	6.3	1.28	-0.45	-10.45
	2,327.0	6.70	184.20	2,313.9	203.5	-203.5	6.1	1.56	0.45	12.95
	2,371.0	6.60	178.80	2,357.6	208.6	-208.6	6.0	1.44	-0.23	-12.27



## Payzone Directional

### End of Well Report



**Company:** NEWFIELD EXPLORATION  
**Project:** USGS Myton SW (UT)  
**Site:** SECTION 32 T8S, R17E  
**Well:** 104-5-9-17  
**Wellbore:** Wellbore #1  
**Design:** Actual

**Local Co-ordinate Reference:** Well 104-5-9-17  
**TVD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**MD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature  
**Database:** EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	D/Leg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	2,414.0	6.40	182.65	2,400.3	213.5	-213.4	5.9	1.11	-0.47	8.95
	2,458.0	6.40	179.30	2,444.1	218.4	-218.3	5.8	0.85	0.00	-7.61
	2,502.0	6.90	178.20	2,487.8	223.5	-223.4	6.0	1.17	1.14	-2.50
	2,546.0	6.80	180.00	2,531.5	228.7	-228.7	6.0	0.54	-0.23	4.09
	2,590.0	6.30	184.49	2,575.2	233.7	-233.7	5.9	1.63	-1.14	10.20
	2,633.0	5.90	180.90	2,617.9	238.3	-238.2	5.6	1.29	-0.93	-8.35
	2,677.0	5.70	180.60	2,661.7	242.8	-242.7	5.6	0.46	-0.45	-0.88
	2,721.0	6.45	185.00	2,705.5	247.4	-247.3	5.3	2.01	1.70	10.00
	2,764.0	6.70	179.55	2,748.2	252.3	-252.3	5.2	1.56	0.58	-12.67
	2,808.0	7.10	184.60	2,791.9	257.6	-257.5	5.0	1.65	0.91	11.48
	2,852.0	6.40	182.20	2,835.5	262.7	-262.7	4.6	1.71	-1.59	-5.45
	2,896.0	6.30	186.40	2,879.3	267.6	-267.5	4.3	1.08	-0.23	9.55
	2,939.0	6.30	181.20	2,922.0	272.3	-272.2	4.0	1.33	0.00	-12.09
	2,983.0	6.90	183.80	2,965.7	277.3	-277.3	3.7	1.52	1.36	5.91
	3,027.0	7.40	180.00	3,009.4	282.8	-282.8	3.6	1.56	1.14	-8.64
	3,071.0	7.50	177.50	3,053.0	288.5	-288.5	3.7	0.77	0.23	-5.66
	3,115.0	7.40	180.60	3,096.6	294.2	-294.2	3.8	0.94	-0.23	7.05
	3,159.0	7.40	179.10	3,140.3	299.9	-299.8	3.8	0.44	0.00	-3.41
	3,203.0	7.20	177.80	3,183.9	305.5	-305.4	3.9	0.59	-0.45	-2.95
	3,246.0	7.50	179.60	3,226.6	311.0	-310.9	4.1	0.88	0.70	4.19
	3,290.0	8.00	183.20	3,270.2	316.9	-316.9	3.9	1.58	1.14	8.18
	3,334.0	7.80	184.40	3,313.7	322.9	-322.9	3.5	0.59	-0.45	2.73
	3,378.0	7.70	180.10	3,357.3	328.8	-328.8	3.3	1.34	-0.23	-9.77
	3,422.0	7.00	179.00	3,401.0	334.5	-334.4	3.3	1.62	-1.59	-2.50
	3,465.0	7.50	183.40	3,443.6	339.9	-339.9	3.2	1.74	1.16	10.23
	3,509.0	7.00	177.70	3,487.3	345.4	-345.4	3.1	1.99	-1.14	-12.95
	3,553.0	7.50	180.80	3,530.9	351.0	-351.0	3.2	1.44	1.14	7.05



# Payzone Directional

## End of Well Report



**Company:** NEWFIELD EXPLORATION  
**Project:** USGS Myton SW (UT)  
**Site:** SECTION 32 T8S, R17E  
**Well:** 104-5-9-17  
**Wellbore:** Wellbore #1  
**Design:** Actual

**Local Co-ordinate Reference:**  
**TVD Reference:** Well 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**MD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature  
**Database:** EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	D Leg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	3,597.0	7.60	178.60	3,574.6	356.7	-356.7	3.2	0.70	0.23	-5.00
	3,641.0	7.30	180.00	3,618.2	362.5	-362.4	3.3	0.80	-0.68	3.18
	3,684.0	6.90	180.50	3,660.9	367.8	-367.8	3.3	0.94	-0.93	1.16
	3,728.0	6.00	177.00	3,704.6	372.7	-372.7	3.4	2.23	-2.05	-7.95
	3,772.0	6.10	175.10	3,748.3	377.3	-377.3	3.7	0.51	0.23	-4.32
	3,816.0	6.20	177.60	3,792.1	382.0	-382.0	4.0	0.65	0.23	5.68
	3,860.0	6.40	174.60	3,835.8	386.9	-386.8	4.3	0.88	0.45	-6.82
	3,904.0	5.90	171.90	3,879.6	391.6	-391.5	4.9	1.31	-1.14	-6.14
	3,948.0	6.20	172.80	3,923.3	396.2	-396.1	5.5	0.72	0.68	2.05
	3,992.0	5.90	172.20	3,967.1	400.8	-400.7	6.1	0.70	-0.68	-1.36
	4,036.0	6.00	175.00	4,010.8	405.3	-405.2	6.6	0.70	0.23	6.36
	4,079.0	6.60	179.90	4,053.6	410.0	-410.0	6.8	1.87	1.40	11.40
	4,123.0	6.40	176.30	4,097.3	415.0	-414.9	7.0	1.03	-0.45	-8.18
	4,167.0	6.30	176.70	4,141.0	419.9	-419.8	7.3	0.25	-0.23	0.91
	4,211.0	6.90	181.90	4,184.7	424.9	-424.8	7.3	1.92	1.36	11.82
	4,255.0	7.00	177.20	4,228.4	430.2	-430.2	7.4	1.31	0.23	-10.68
	4,299.0	7.30	176.50	4,272.1	435.7	-435.6	7.7	0.71	0.68	-1.59
	4,342.0	7.40	177.50	4,314.7	441.2	-441.1	8.0	0.38	0.23	2.33
	4,386.0	7.00	177.30	4,358.4	446.7	-446.6	8.2	0.91	-0.91	-0.45
	4,430.0	6.90	178.80	4,402.0	452.0	-452.0	8.4	0.47	-0.23	3.41
	4,474.0	6.50	182.40	4,445.7	457.2	-457.1	8.3	1.32	-0.91	8.18
	4,517.0	6.60	178.20	4,488.5	462.1	-462.0	8.3	1.14	0.23	-9.77
	4,561.0	6.30	183.70	4,532.2	467.0	-466.9	8.2	1.56	-0.68	12.50
	4,605.0	6.50	186.00	4,575.9	471.9	-471.8	7.8	0.74	0.45	5.23
	4,649.0	6.30	186.00	4,619.6	476.7	-476.7	7.3	0.45	-0.45	0.00
	4,693.0	6.80	187.90	4,663.3	481.7	-481.7	6.7	1.24	1.14	4.32
	4,736.0	7.50	183.00	4,706.0	487.0	-487.0	6.2	2.16	1.63	-11.40



## Payzone Directional

### End of Well Report



**Company:** NEWFIELD EXPLORATION  
**Project:** USGS Myton SW (UT)  
**Site:** SECTION 32 T8S, R17E  
**Well:** 104-5-9-17  
**Wellbore:** Wellbore #1  
**Design:** Actual

**Local Co-ordinate Reference:** Well 104-5-9-17  
**TVD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**MD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature  
**Database:** EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	D/Leg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
104-5-9-17 TGT	4,780.0	6.90	188.10	4,749.7	492.5	-492.5	5.7	1.99	-1.36	11.59
	4,824.0	7.70	185.30	4,793.3	498.0	-498.0	5.0	1.99	1.82	-6.36
	4,868.0	7.50	185.80	4,836.9	503.8	-503.8	4.5	0.48	-0.45	1.14
	4,911.0	7.10	189.40	4,879.6	509.2	-509.2	3.8	1.41	-0.93	8.37
	4,955.0	7.10	183.30	4,923.2	514.6	-514.6	3.2	1.71	0.00	-13.86
	4,999.0	6.90	180.90	4,966.9	520.0	-520.0	3.0	0.81	-0.45	-5.45
	5,005.5	6.88	181.41	4,973.4	520.8	-520.8	2.9	0.98	-0.25	7.85
	5,043.0	6.80	184.40	5,010.6	525.2	-525.2	2.7	0.98	-0.22	7.97
	5,087.0	6.40	182.00	5,054.3	530.2	-530.3	2.4	1.10	-0.91	-5.45
	5,131.0	6.40	182.80	5,098.0	535.1	-535.2	2.2	0.20	0.00	1.82
	5,174.0	5.50	181.90	5,140.8	539.6	-539.6	2.0	2.10	-2.09	-2.09
	5,218.0	5.20	187.20	5,184.6	543.7	-543.7	1.7	1.31	-0.68	12.05
	5,262.0	5.50	184.70	5,228.4	547.7	-547.8	1.3	0.86	0.68	-5.68
	5,307.0	5.90	183.50	5,273.2	552.2	-552.3	1.0	0.93	0.89	-2.67
	5,352.0	6.20	183.20	5,317.9	556.9	-557.0	0.7	0.67	0.67	-0.67
	5,393.0	6.90	181.90	5,358.7	561.6	-561.7	0.5	1.75	1.71	-3.17
	5,437.0	8.00	175.40	5,402.3	567.3	-567.4	0.7	3.15	2.50	-14.77
	5,481.0	9.10	175.00	5,445.8	573.8	-573.9	1.2	2.50	2.50	-0.91
	5,525.0	10.10	172.20	5,489.2	581.1	-581.2	2.0	2.51	2.27	-6.36
	5,569.0	10.10	172.30	5,532.5	588.8	-588.8	3.1	0.04	0.00	0.23
	5,613.0	8.95	172.50	5,575.9	596.0	-596.0	4.0	2.61	-2.61	0.45
	5,656.0	9.00	174.40	5,618.4	602.7	-602.7	4.8	0.70	0.12	4.42
	5,700.0	8.75	175.70	5,661.9	609.5	-609.4	5.4	0.73	-0.57	2.95
	5,744.0	8.10	175.10	5,705.4	615.9	-615.9	5.9	1.49	-1.48	-1.36
	5,788.0	7.87	174.70	5,749.0	622.0	-622.0	6.4	0.54	-0.52	-0.91
	5,831.0	7.70	173.20	5,791.6	627.8	-627.8	7.1	0.62	-0.40	-3.49



# Payzone Directional

## End of Well Report



**Company:** NEWFIELD EXPLORATION  
**Project:** USGS Myton SW (UT)  
**Site:** SECTION 32 T8S, R17E  
**Well:** 104-5-9-17  
**Wellbore:** Wellbore #1  
**Design:** Actual

**Local Co-ordinate Reference:**  
**TVD Reference:** Well 104-5-9-17  
**MD Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**North Reference:** 104-5-9-17 @ 5255.0ft (NDSI SS #2)  
**Survey Calculation Method:** True  
**Database:** Minimum Curvature  
 EDM 2003.21 Single User Db

Survey	MD (ft)	Inc (°)	Azi (azimuth) (°)	TVD (ft)	V. Sec (ft)	N/S (ft)	E/W (ft)	D/Leg (°/100ft)	Build (°/100ft)	Turn (°/100ft)
	5,875.0	7.20	174.90	5,835.2	633.5	-633.4	7.7	1.24	-1.14	3.86
	5,919.0	7.40	175.20	5,878.8	639.0	-639.0	8.1	0.46	0.45	0.88
	5,963.0	6.55	176.00	5,922.5	644.4	-644.3	8.6	1.94	-1.93	1.82
	6,007.0	6.60	178.40	5,966.2	649.4	-649.4	8.8	0.63	0.11	5.45
	6,050.0	6.20	176.10	6,008.9	654.2	-654.1	9.0	1.10	-0.93	-5.35
	6,094.0	6.00	177.20	6,052.7	658.9	-658.8	9.3	0.53	-0.45	2.50
	6,138.0	5.60	177.20	6,096.5	663.3	-663.3	9.5	0.91	-0.91	0.00
	6,178.0	4.92	171.20	6,136.3	667.0	-666.9	9.9	2.18	-1.70	-15.00
	6,227.0	4.92	171.20	6,185.1	671.1	-671.0	10.5	0.00	0.00	0.00

Checked By: \_\_\_\_\_

Approved By: \_\_\_\_\_




Date: \_\_\_\_\_





Project: USGS Myton SW (UT)  
Site: SECTION 32 T8S, R17E  
Well: 104-5-9-17  
Wellbore: Wellbore #1  
Design: Actual

Azimuths to True North  
Magnetic North: 11.13°  
Magnetic Field  
Strength: 52150.4snT  
Dip Angle: 65.78°  
Date: 11/8/2012  
Model: IGRF2010



Design: Actual (104-5-9-17/Wellbore #1)

Created By: *David Well* Date: 11:42, August 19 2013

THIS SURVEY IS CORRECT TO THE BEST OF  
MY KNOWLEDGE AND IS SUPPORTED  
BY ACTUAL FIELD DATA

## Summary Rig Activity

Job Category	Job Start Date	Job End Date
<b>Daily Operations</b>		
Report Start Date 9/9/2013	Report End Date 9/9/2013	24hr Activity Summary Run CBL, Test casing, blinds, and Frac Valve. Perforate.
Start Time	End Time	Comment
	07:00	SDFN.
Start Time	End Time	Comment
	09:00	RU Perforators. RIH Run CBL From 6142' to Surface. Cement Top @ 32'
Start Time	End Time	Comment
	11:00	RU S&S Press tester Press test Csg. Csg Valves, Blind Ram, & Frac Valve Low 300 psi High 4300 psi
Start Time	End Time	Comment
	12:30	RU Perforators RIH Perforate CP-4 Sand @ 5861--64', 5850-51', 5840431', W/ 3-1/8 Csg Guns 2SPF (16 shots)
Start Time	End Time	Comment
	00:00	SDFN.
Report Start Date 9/10/2013	Report End Date 9/10/2013	24hr Activity Summary Frac Stage 1,2,3,4,
Start Time	End Time	Comment
	07:00	SDFN.
Start Time	End Time	Comment
	07:30	Stage#1Frac CP sds (16 holes) W/ 45,060# 20/40 white Sand @ 3167 max psi 2273 avg psi. 34.5 max BPM, 33.4 avg BPM. ISIP 1825 psi. FG.77 519 total bbls pumped
Start Time	End Time	Comment
	09:00	Stage #2 RIH Set CFT Plug @ 5380' perforate the A-3 formation @ 5302-04', 5289-90', A-1 @ 5257-59', W/ 3-1/8" Csg guns 3SPF (15 Holes)
Start Time	End Time	Comment
	09:30	Stage#2 Frac A sds W/ 39,880# 20/40 White Sand @ 2886 max psi, 2435 avg psi. 30.1 max BPM, 28.4 avg BPM. ISIP 2002 psi FG.83. 442 total bbls pumped
Start Time	End Time	Comment
	11:30	Stage#3 RIH Set CFT Plug @ 5190' perforate the B-2 formation @ 5111-15', C-Sand @ 4967-68', 4960-61', W/ 3-1/8" Csg guns 3SPF (18 Holes)
Start Time	End Time	Comment
	12:00	Stage#3 Frac B-2 & C-Sands W/ 50,500# 20/40 White Sand @ 2824 max psi, 2352 avg psi. 36.5 max BPM, 36.2 avg BPM. ISIP 2063 psi FG.86. 564 total bbls pumped
Start Time	End Time	Comment
	13:00	Stage #4 RIH Set CFT Plug @ 4910' perforate the D-2 formation @ 4858-59', ; D-1 @ 4797-80', 4960-61', W/ 3-1/8" Csg guns 2SPF (14 Holes)
Start Time	End Time	Comment
	13:30	Stage#4 Frac D sds W/ 40,080# 20/40 White Sand @ 2691 max psi, 2336 avg psi. 30.2 max BPM, 29.6 avg BPM. ISIP 2262 psi FG.92. 467 total bbls pumped
Start Time	End Time	Comment
	14:30	Stage #5 RIH Set CFT Plug @ 4420' perforate the GB-6 formation @ 4342-43', 4339-40', 4331-33', 4320-22', GB-4 @ 4282-83', 4278-79', 4273-74', W/ 3-1/8" Csg guns 2SPF (18 Holes)
Start Time	End Time	Comment
	00:00	SDFN.
Report Start Date 9/11/2013	Report End Date 9/11/2013	24hr Activity Summary Finish frac Flow Back Well. Set kill Plug
Start Time	End Time	Comment
	07:00	SDFN.
Start Time	End Time	Comment
	07:30	Stage#5 Frac GB- sds W/ 70,010# 20/40 White Sand @ 2863 max psi, 2270 avg psi. 37.2 max BPM, 35.7 avg BPM. ISIP 1915 psi FG.90. 618 total bbls pumped

RECEIVED: Oct. 15, 2013

NEWFIELD



Well Name: GMBU 104-5-9-17

## Summary Rig Activity

Start Time	07:30	End Time	09:30	Comment
Start Time	09:30	End Time	10:30	Comment
Start Time	10:30	End Time	00:00	Comment
Report Start Date	9/12/2013	Report End Date	9/12/2013	24hr Activity Summary
Start Time	00:00	End Time	07:00	Set KP @ 4160', N/U & PT BOP
Start Time	07:00	End Time	10:00	Comment
Start Time	10:00	End Time	15:00	Comment
Start Time	15:00	End Time	00:00	Comment
Report Start Date	9/13/2013	Report End Date	9/13/2013	24hr Activity Summary
Start Time	00:00	End Time	07:00	P/U RIH w/ BRS, tag & D/O kp and 1 flow through
Start Time	07:00	End Time	08:00	Comment
Start Time	08:00	End Time	10:30	Comment
Start Time	10:30	End Time	11:30	Comment
Start Time	11:30	End Time	11:48	Comment
Start Time	11:48	End Time	15:48	Comment
Start Time	15:48	End Time	18:48	Comment
Start Time	18:48	End Time	00:03	Comment
Report Start Date	9/16/2013	Report End Date	9/16/2013	24hr Activity Summary
Start Time	00:00	End Time	07:00	Cont. to D/O CBP's C/O to PBTD @ 6194' well is flowing Pooch above perfs and flow overnight recovered 150 bbls oil & 30 bbls wtr.

NEWFIELD



Well Name: GMBU 104-5-9-17

## Summary Rig Activity

Start Time	07:00	End Time	09:00	Comment
				CHECK PSI CSG-500 TBG-SLIGHT FLOW, OPEN UP & BLEED WELL TO FRAC TANK, PUMP 10 BW DOWN TBG TO CLEAR BIT, RIH w/ 18-JNTS TBG FROM DERRICK, P.U. 15-JNTS & TAG 3rd CFP @ 4910' (No Fill)
Start Time	09:00	End Time	14:00	Comment
				R.U. POWER SWIVEL, MAKE UP HOBBLES ON PUMP LINES, DRILL UP 3rd CFP (21 Min) SWIVEL DOWN, TAG 2nd CFP @ 5190' DRILL UP (19 Min) SWIVEL DOWN, TAG FILL @ 5330' (50' of Fill) CLEAN OUT TO 1st CFP @ 5380' DRILL UP (23 Min) R.D. SWIVEL, P.U. & RIH w/ TBG, TAG FILL @ 6091' (93' of Fill) CLEAN OUT TO PBTD @ 6194'
Start Time	14:00	End Time	15:00	Comment
				CIRC WELL w/ 140 BW 7% KCL UNTIL RETURNS WERE CLEAN, R.D. SWIVEL, L.D. 8-JNTS TBG
Start Time	15:00	End Time	16:00	Comment
				CSG WOULDN'T DIE, FLOWED 35 BBLs OIL TO Z-TANK
Start Time	16:00	End Time	17:30	Comment
				L.D. 51-JNTS 2 7/8" J-55 TBG, EOT @ 4222', STRIP ON & LAND TBG ON HANGER
Start Time	17:30	End Time	18:00	Comment
				FILL TREATER w/ H2O
Start Time	18:00	End Time	00:00	Comment
				SDFN.
Report Start Date	9/17/2013	Report End Date	9/17/2013	24hr Activity Summary
Start Time	00:00	End Time	07:00	Comment
				BOPE N/U wellhead P/U RIH w/ pump and btm 7/8 & 3/4" rods P/U polish rod SWIFN
Start Time	07:00	End Time	08:30	Comment
				SDFN.
Start Time	08:30	End Time	10:30	Comment
				Travel time / JSP MEETING - P.U. RODS
Start Time	10:30	End Time	12:00	Comment
				CHECK PSI CSG 125 ON A 26 CHOKE, CIRC 100 BW TO KILL WELL
Start Time	12:00	End Time	14:30	Comment
				STRIP TBG HANGER OUT, POOH w/ 132-JNTS 2 7/8" J-55 TBG, "X" NIPPLE, 1-JNT TBG, POBS & BIT
Start Time	14:30	End Time	15:30	Comment
				M.U. & RIH w/ PURGE VALVE, 3-JNTS TBG, DESANDER, 4' PUP JNT, 1-JNT T BG, S/N, 1-JNT TBG, T/A, 128-JNTS TBG, P.U. 56-JNTS 2 7/8" J-55 TBG, 4' PUP, TBG HANGER, SET T/A FROM FLOOR, LAND HANGER
Start Time	15:30	End Time	17:00	Comment
				R.D. TONGS & HANDRAILS, R.U. FLOOR, N.D. DOUBLE 2 7/8" PIPE RAMS, N.D. BLIND RAM
Start Time	17:00	End Time	18:30	Comment
				REVERSE CIRC WELL w/ 135 BW, BLEED TBG & CSG OFF
				PULL TBG HANGER & 4' PUP JNT, INSTALL RODUCTION HANGER LAND TBG, N.U. WELL HEAD, X-OVER TO ROD EQUIP





Well Name: GMBU 104-5-9-17

## Summary Rig Activity

Start Time	18:30	End Time	21:00
Comment			
FINISH PREP RODS, M.U. & RIH w/ 2 1/2" x 1 3/4" x 24' RHAC w/ GROOVED PLUNGER, 30-7/8" 8per, 131-3/4" 4per, P.U. POLISH ROD & SWI, CLEAN UP, S.D.F.N.			
Start Time	21:00	End Time	00:00
Comment			
SDFN.			
Report Start Date	Report End Date	24hr Activity Summary	
9/18/2013	9/19/2013	Cont. in hole w/ rods R/U NOV hyd pumping unit PWOP	
Start Time	00:00	End Time	05:30
Comment			
SDFN.			
Start Time	05:30	End Time	07:00
Comment			
Travel			
Start Time	07:00	End Time	09:00
Comment			
BLEED WELL OFF TBG & CSG 450 PSI, CONT RIH w/ RODS AS DETAILED IN REPORT, SEAT PUMP, SPACE OUT, HANG POLISH ROD			
Start Time	09:00	End Time	12:00
Comment			
R.U. HYDRAULIC PUMPING UNIT, ADD 18' POLISH ROD, HANG OFF, PREP TO RIG DOWN			
Start Time	12:00	End Time	12:30
Comment			
DROP LINES, RIG DOWN, WRAP LINE, PULL AHEAD			
Start Time	12:30	End Time	00:00
Comment			
SDFN.			